

34-25-38W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

500 East Murdock,


Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
Farm- Max Cohen "B" No. 1

SEC. 34 T. 25 R. 38W
SW SW SW NE
150' N of SL, 150'
E of WL of NE 1/4

County Kearny KANSAS

Total Depth. 2640
Comm. 8-22-51 Comp. 9-9-51
Shot or Treated.
Contractor.
Issued. 12-15-51



CASING:
10 3/4" 606' cem w/400 sxs.
7" 2624' cem w/300 sxs.

Elevation. 3217(m)
3214
3218 (2nd)

Production. 23,360,000 gas

Figures indicate Bottom of Formations.

surface sand, clay	150
blue clay	220
clay, gravel	345
gravel	390
clay, shale	430
blue clay, shale	570
red bed	680
sand, shale	720
shale, gyp	760
shale	1120
gyp	1190
shale, gyp	1245
anhydrite	1390
shale	1445
shale, gyp	1550
gyp, anhydrite	1825
shale	2060
shale, lime	2205
lime	2395
lime, shale	2400
lime	2455
lime, dolomite	2575
lime	2640
Total depth	

Dowell Inc. Acidized as follows:
w/2500 gal 15% flushed
w/4210 gal wtr.
Towanda w/3500 gal 15%
flushed w/600 gal wtr.
2552-2499 w/3000 gal 15%
flushed w/600 gal wtr.
2500-2447 w/3000 gal 15%
flushed w/600 gal wtr.
All zones w/13000 gal 7 1/2%
flushed w/4410 gal wtr.
All zones w/9000 gal 7 1/2%
flushed w/4200 gal wtr.
All zones w/5000 gal 7 1/2%
flushed w/3780-gal wtr.

Tops:	
Herington-Krider	2448
Winfield	2503
Towanda	2568
Ft. Riley	2624

Schlumberger ran to 2640
Schlumberger gun perf.
w/6 SPF as follows;
Herington-Krider 2453-2473
2476-2481
2486-2491
Winfield 2503-2527
2535-2542
Towanda 2572-2598
2610-2620