

MAP NO. _____ ELEV. 3310 KB, 3304 GL
 STATE Kansas COUNTY Hamilton SEC. 26 Twp 25S Rge 39W
 OPERATOR Kansas-Nebraska Natural Gas Co. LOC. C SE/4
 WELL NO. 1 FARM NAME Englert FT. FROM _____ LINE _____
 POOL Hugoton FT. FROM _____ LINE _____
 FR. 10-28-60 SPUD 10-27-60 COMP. 12-2-60
 CONT./GEOL. Davis Drlg. Tools

COMPLETION RECORD

NAME PRODUCING INTERVAL FROM — TO PERF. W/HOLES TREATMENT RECORD

a _____
 b _____
 c _____
 d _____

a I. P. OIL/DIST. _____ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. _____
 b " " " " " "
 c " " " " " "
 d _____

D&A

D & A | 24

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBTD _____ TD 3062

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD SIZE	DEPTH	W/SAX.
<u>8 5/8</u>	<u>302</u>	<u>225</u>			
<u>5 1/2</u>	<u>3058</u>	<u>225</u>			

OPERATOR Kansas-Nebraska Natr. WELL NO. #1 Englert ELEV 3304 GL

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA.
			Krider	2462	
			Winfield	2512	+798
			Upper Ft. Riley	2584	
			Lower Ft. Riley	2624	
			Council Grove	2800	+510

TD 3060

DST #1 (CG) 2774-3060, op 1 hr 15 mins, rec 70' mud, FP 20-70,
 SIP 1385-1530/30 mins.

Ran Schl Log.

LWT #1 @ 1990, op 1 hr, rec 3800' cc wtr, SIP 1812/30 mins.

5½" @ 3058 w/225. RUCT, CO 3040 PBD

Perf (Council Grove) 56/3000-14 & 40/3020-30, NS, 1000 A - 15%,
 Swb on load, rec load - NS.

Perf (Council Grove) 60/2898-2908, wtr.

Perf (Council Grove) 72/2802-14, wtr.

BP @ 2600


Perf (Krider) 66/2464-75

Perf (Winfield) 72/2518-30

Perf (Winfield) 36/2538-44

FSG 1000 A, rec load SSG, TSTM, Frac 40,000 gal 5% A X 40,000 sd.

Rec load, SSG, TSTM + 4 BFWPH
D & A.



ASS. NO.	DATE
1001	10/10/50
1002	10/11/50
1003	10/12/50
1004	10/13/50
1005	10/14/50