

KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 075 — 20,281
County Number

Operator

Amoco Production Co.

Address

P. O. Box 432 Liberal, Kansas 67901

Well No.

#1

Lease Name

J. A. Englert Gas Unit

Footage Location

1980 feet from ~~NN~~ (S) line 1980 feet from (W) line

Principal Contractor

Service Drilling Company

Geologist

Spud Date

05-08-79

Total Depth

3005

P.B.T.D.

None

Date Completed


06-22-79

Oil Purchaser

S. 22 T. 25 R. 39 ~~X~~ W

Loc. 1980' FSL X 1980' FWL

County Hamilton

640 Acres
NLocate well correctly
3278

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24	627	Howco Lite Class H	200 150	2% CACL 6% GEL 3% CACL
Production	7 7/8"	5 1/2"	14	3005	Howco Lite 50-50 POZ	600 150	1/4# Flakes 18% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.5 Jet	2698-2715
			2	.5 Jet	2746-2760
			2	.5 Jet	2769-2775
			2	.5 Jet	2788-2802

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	2812	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/2500 gal 15% HCL. Frac w/100,000 gal treated water and 200,000# riversand.	Council Grove Perfs. 2698'-2802'

INITIAL PRODUCTION

Date of first production 06-22-79	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	bbls. 1300 MCF bbls. CFPB
Disposition of gas (vented, used on lease or sold) Waiting on Pipeline connection	Producing interval (s) See above Council Grove Perfs

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Date Received	 Signature	Gale McCord
	Administrative Supervisor	
	Title	
	July 30, 1979	Date