

WICHITA BRANCH

KANSAS DRILLERS LOG

API No. 15 — 075 — 20,211
 County Number

S. 34 T. 25S R. 39 W
 Loc. 2310' FEL & 2310' FSL
 County Hamilton

Operator
 Amoco Production Company

Address
 P. O. Box 432, Liberal, Kansas 67901


Well No. 1 Lease Name Overbey

Footage Location
 2310 feet from (N) (S) line 2310 feet from (E) (W) line

Principal Contractor Service Drilling Company Geologist

Spud Date 01-04-78 Total Depth 3010 P.B.T.D. 3003

Date Completed 03-09-78 Oil Purchaser



Locate well correctly
 Elev.: Gr. 3344
 DF _____ KB _____

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24#	629	Class "H"	385	3% CACL
Production	7 7/8	5 1/2	14#	3009	Special	800	18% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1/2	2770-89
TUBING RECORD					2805-20
					2830-36
Size 2 3/8	Setting depth 2917	Packer set at			2849-61
					2870-89

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fraced with 100,000 gal treated water and 20,000# river sand.	2770-2889

INITIAL PRODUCTION

Date of first production 03-09-78	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. 2300 MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) Waiting on pipeline connection	Producing interval (s) 2770-2889

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Amoco Production Company DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas

Well No. 1 Lease Name Overbey

S 34 T 25 S R 39 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Sand & Rocks	0	120		
Sand, Shale, Red Bed	120	629		
Sand, Gypsum, Red Bed	629	836		
Sand, Shale, Red Bed	836	1356		
Sand & Lime	1356	1980		
Shale & Lime	1980	2320		
Lime	2320	2724		
Shale & Lime	2724	2880		
Lime	2880	3010		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Gale McCord
Signature

Gale McCord

Administrative Supervisor

Title

March 15, 1978

Date