


Company- MUSGROVE PETROLEUM CORPORATION
Farm- Bray No. 1

SEC. 26 T 25 R. 41W
NW NW NW

26-25-41W

County Hamilton KANSAS



Total Depth. 5605'
Comm. 2-1-55 Comp. 3-1-55
Shot or Treated.
Contractor. Musgrove Petro. Corp.
Issued. 4-2-55

CASING:

13 3/8" 720' cem w/600 sx

Elevation. 3542' RB

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	30
post rock	40
shale	515
hard lime	575
sand	700
shale	720
red bed & sand	975
sandy lime	1080
red bed	1220
red bed & lime streaks	1700
red bed	2043
anhydrite & red bed	2160
red bed & lime streaks	2400
red bed & lime	2520
red shale, shells & lime streaks	2690
red bed & lime	3032
lime & st. red bed	3094
lime & red shale strks	3154
red shale & lime	3180
shale & lime	3335
red shale & lime	3422
shale & lime	3923
lime	4440
lime & shale	4516
lime	4652
lime & shale	4700
sand & lime	4730
lime & shale	4828
lime	4929
lime & shale	4975
lime & St. sand	5004
lime, sandy lime & shale	5036
shale, lime & sand & chert	5087
lime & shale	5125
sandy shale & lime	5205
sandy shale	5275
shale & lime	5230
shale & sandy lime	5449
sandy lime	5470
sandy lime & shale & chert	5492
sand, lime & chert	5531
lime & chert	5605
Total Depth	
Tops: Scout	
Ft. Riley	2685
Wreford	2805

Topeka 3500
Heebner 3886
Lansing 3920
Base Kansas City 4487
Atoka 4902
Morrow 5146
Mississippi 5455
St. Louis 5486