

6-25-42W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- UNITED PRODUCING
Farm- Frank Helfrich No. 3

SEC. 6 T. 25 R. 42W
C SW SE

Total Depth. 5179'
Comm. 10-1-55 Comp. 10-22-55
Shot or Treated.
Contractor. R. W. Rine Drlg.
Issued. 6-23-56

County Hamilton
KANSAS



Elevation. 3598'

CASING:

13 3/8" 606' cem w/500 sx

Production. Dry

Figures Indicate Bottom of Formations.

cleache and blue shale	470
rock	625
shale, shells & red bed	1080
red bed, gyp and salt	1550
red bed and gyp	1750
gyp and shale	1935
red bed & gyp	2380
red bed, gyp and sand	2610
lime and shale	3375
lime	3450
lime and shale	3780
lime	3835
lime and shale	3995
lime	4110
lime and shale	4190
lime	5064
shale	5179
Total Depth	

Tops: Scout	
Topeka	3445
Heebner	3764
Lansing	3790
Marmaton	4581
Cherokee	4730
Morrow Zone	4994
1st Morrow Sand	5000
2nd Morrow Sand	5145