

#1

33-25-42W
SE NW SE

MAR 21 1970

CHAMPLIN PETROLEUM COMPANY

33-25-42W

MICHAEL B. SANDERS #1
Hamilton County, Kansas

COMMENCED OPERATIONS: 1-16-70
COMPLETED OPERATIONS: 2-6-70

Last hole / 200'

DRILLERS LOG

1-16-70	0 - 444	Sand, Gypsum & Red Bed.
1-17-70	444 - 731	Sand, Gypsum & Red Bed.
1-18-70	731 - 1290	Red Bed.
1-19-70	1290 - 2220	Red Bed, Sand, Shale & Anhydrite.
1-20-70	2220 - 2838	Anhydrite, Shale, Sand & Lime.
1-21-70	2838 - 3185	Shale, Anhydrite & Lime.
1-22-70	3185 - 3392	Shale & Lime.
1-23-70	3392 - 3660	Shale & Lime.
2-4-70	3660 - 3212	Lime & Gypsum.
2-5-70	3212 - 3259	Lime & Gypsum.


Tapeka R.J.D. 3416 3660

elev. 3454' DF

CASING RECORD

1-17-70 Ran 18 jts. 20# 8 5/8" casing. Set @ 732'.
Cemented with 220 sacks lt. wt., 2% c.c.
and 100 sacks common, 2% cc.

2-6-70 ~~Ran drill pipe.~~ Spotted 35 sacks pozmix
@ 700', 15 sacks @ 45' and spotted top plug.



*The log to 3259' (top of fish) was for 1st hole which was lost due to stuck drill pipe at 3660'.
The log to 5460' was for the 2nd hole after rig was skidded 150' East of original location.*