

24 - 25 - 5W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **TEXSTAR PETROLEUM**
Farm- O. H. Blocker No. 1

SEC. 24 T. 25 R. 5W
C SE SE
530' FSL & 620' FEL

Total Depth. 4133'
Comm. 8-20-63 Comp. 9-2-63
Shot or Treated.
Contractor. Leben Drlg.
Issued. 6-6-64

County Reno
KANSAS



CASING:

8 5/8" 263' cem w/ 225 sx
5 1/2" 4133'

Elevation 1543' KR

Production. Temp ABDN

Figures Indicate Bottom of Formations.

surface soil & gravel	50
shale & shells	262
shale	690
anhydrite	720
shale & lime	980
lime	1500
shale & lime	2110
lime & shale	2545
lime	3158
lime, chert, shale	3230
lime	3423
lime & shale	3480
shale & lime	3560
lime & chert	3573
conglomerate	3585
chat	3625
lime & chert	3627
Mississippi chat	3658
lime	3665
Mississippi lime	3705
lime & chert	3791
lime	3844
shale (Kinderhook)	3875
shale	4008
Viola	4010
shale	4032
lime	4048
sand	4117
sandy shale	4133 RTD
Total Depth	

TOPS: SCOUT	
Heebner	2580
Toironto	2600
Brown Lime	2798
Lansing	2832
Mississippi	3558
Mississippi Chat	3590
Kinderhook	3842
Viola	4030
Simpson	4044