

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-25-6W

Company- RUPP-FERGUSON OIL CO.
Farm- Elward Estate No. 1

SEC. 15 T. 25 R. 6W
NE NE NE

Total Depth. 4118

Comm. 10-21-55

Comp. 11-5-55


Shot or Treated.

Contractor. Rupp-Ferguson Oil Co.

Issued. 12-10-55

County Reno

KANSAS



8 5/8 C.SING: 251' w/ 260 sx cmt.

Elevation. 1508 KB

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	10
sand & gravel	60
red rock & shale	194
shale	525
salt	775
lime	975
shale & lime	1970
shale & shells	2230
lime & shale	2590
sand, lime & shale	2748
sand & lime	2910
lime & shale	3013
lime	3200
lime & shale	3477
Mississippi	3567
lime & shale	3614
lime	3634
Mississippi	3738
lime & shale	3769
shale	3895
shale & lime	3955
lime, shale & sand	4024
Simpson	4057
sand	4081
Arbuckle	4118
Total Depth	

ELECTRIC LOG TOPS:

Brown lime	2837
Lansing-KC	2870
Mississippian	3528
Kinderhook	3748
Chattanooga shale	3916
Misener	3948
Viola	3950
Simpson sand	3984
Arbuckle	4072

DST #1: 3182-3200, open 1 hr. rec.
28' drlg. mud, few specks oil, BHP
950#

DST #2: 3530-50, open 1½ hrs. gas to
surf. 20 min. too weak to gauge, rec.
45' drlg. mud, BHP 1020#

DST #3: 3550-65, open 1 hr. rec. 90'.
GCM, 180' GCMW, 60' MW, BHP 900#

DST #4: 3940-55, open 1 hr. rec.
115' muddy wtr. BHP 1410#