


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO.
Farm- Tredway No. 1

SEC. 34—~~36~~ T. 26 R. 10W
SW NW NE

Total Depth. 4450'
Comm. 4-7-59 Comp. 4-20-59
Shot or Treated.
Contractor. Aylward Drlg.
Issued. 6-6-59

County Reno
KANSAS



CASING:

8 5/8" 282' cem w/250 sx.

Elevation. 1709' RB

Production. Dry

Figures Indicate Bottom of Formations.

sand	85
red rock	282
red bed	850
salt & blue shale	1150
shells & shale	1310
shale w/shells	1440
lime & shale	1465
lime w/vry little shale	1565
lime & shale	2315
shale	2575
shale & lime	2860
shale w/lime	2868
sand & shale	3200
sandy lime & shale	3340
sandy lime w/shale	3500
lime & shale	3525
lime	3951
cherty lime & shale	4023
lime	4049
lime & shale	4115
shale	4184
shale & lime	4206
lime	4260
cherty lime	4329
cherty lime & shale	4341
shale & sandy shale	4429
lime & chert	4450 RTD
Total Depth	

TOPS:

Heebner	3322
Toronto	3335
Douglas	3342
Brown Lime	3499
Lansing	3509
Base Kansas City	3880
Mississippian	4009
Kinderhook	4043
Maquoketa	4193
Viola	4260
Simpson	4341
Arbuckle	4429

DST 4005-23' op 1 hr, wk bl 5 mins,
rec. 20' mud, IBHP 1595#/20 mins,
FBHP 875#/30 mins, FP 22#-35#.

Logged.