

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

28-26-11W


Company- OIL CAPITOL CORPORATION
Farm- Eyers No. 1

SEC. 28 T. 26 R.11W
SW NE SW

Total Depth. 4483
Comm. 7-7-55 Comp. 7-25-55
Shot or Treated.
Contractor. Iron Drilling Co.
Issued. 9-3-55

County Pratt

KANSAS



8 5/8 CASING:
332' w/ 200 sx cmt.

Elevation. 1832 KB

Production. Dry

Figures indicate Bottom of Formations.

subsoil & sand	180	DST #2: 4081-91, open 1 hr. wk. bl.
red bed	380	rec. 15' mud, NS, BHP 0#/20 min.
red bed & shale	605	
red bed	705	DST #3: 4205-80, open 1 hr. strong
anhydrite	730	blow, gas to surf. 7 min. gauged
shale	1040	1,140 MCF/GPD, rec. 1170' fluid, top
shale & shells	1230	30' OCM, next 240' gas, next 200'
shale & lime streaks	1270	M&WCO, approx 25% oil, bottom 700'
shale & shells	1440	SW, IFP 410#, FFP 490#, BHP 710#/
salt	1520	20 min.
shale & shells	1655	
shale & lime	1700	
lime	1780	
lime & shale	3475	
lime	3570	
lime & shale	3635	Electric Log TD 4481
lime	3713	
K. C. lime	3746	TOPS:
lime & shale	3767	Topeka 3076
lime	3815	Leebner 3428 3428
K. C. lime	3855	Brown lime 3609 3607
lime	3916	Lansing 3625 3623
lime & shale	3955	Mississippian 4079 4077
lime	4022	Kinderhook 4144 4146
lime & shale	4079	Viola 4262 4261
Mississippi chert	4103	Simpson 4361 4359
Mississippi chert & shale	4135	Arbuckle 4443 4443
shale & lime	4163	
shale	4265	DST #1: 3718-46, open 1 hr. wk. bl.
conglomerate	4280	rec. 240' gas, 100' OCM, 60' SW,
cherty dolomite	4293	IFP 30#, FFP 60#, BHP 1120#/20 min.
chert, lime & shale	4312	
lime	4355	
lime & shale	4375	
Simpson sand	4435	
shale & lime	4443	
Arbuckle	4480	
lime	4483	
Total Depth		