


1971 COMPANY H-30, Inc et al.

FARM Simon "A" NO. 2

TOTAL DEPTH 4290'
 COMM. July 24, 1968 COMP. August 4, 1968
 SHOT OR TREATED
 CONTRACTOR H-30, Inc
 ISSUED

COUNTY Leath pratt
 KANSAS



CASING
 20 10
 15 8-5/8" 408' cemented w/ 275 lb cement
 12 6
 13 5-1/2" 4274' cemented w/ 100 lb cement

ELEVATION 1827 KB
 PRODUCTION PMP
 25 BOPD
 MLW

FIGURES INDICATE BOTTOM OF FORMATIONS

| | | | |
|-----------------------|------|-------------------|-------------|
| Clay & Sand | 165 | Cottonwood | 2284 - 457 |
| Clay & Shale | 275 | Base Cottonwood | 2326 - 499 |
| Clay, Shale & Red Bed | 410 | Heebner | 3428 - 1601 |
| Red Bed | 585 | Toronto | 3441 - 1614 |
| Shale & Lime streaks | 1100 | Douglas | 3462 - 1635 |
| Salt & Shale | 1580 | Brown Lime | 3610 - 1783 |
| Shale & Lime streaks | 1810 | Lansing | 3626 - 1799 |
| Lime & Shale | 2465 | Base KC. | 3974 - 2147 |
| Shale & Shells | 2750 | Conglomerate sand | 4060 - 2233 |
| Shale & Lime streaks | 2915 | Mississippi Chert | 4064 - 2237 |
| Shale & Lime | 3085 | Mississippi Lime | 4108 - 2281 |
| Lime & Shale | 3590 | Kinderhook Shale | 4159 - 2332 |
| Lime | 4048 | Viola | 4270 - 2443 |
| Lime & Chert | 4137 | Log T. D. | 4292 - 2455 |
| Lime | 4155 | Rotary T. D. | 4290 - 2453 |
| Lime & Shale | 4270 | | |
| Lime | 4290 | | |
| Rotary T. D. | 4290 | | |

DST 4271-90

over

Log Left

| | |
|------------|------|
| Hebner | 3428 |
| Taranta | 3441 |
| Dauglar | 3462 |
| Br Line | 3610 |
| Fanning | 3626 |
| BKJ | 3974 |
| Miss. Lkt | 4064 |
| Kinderhook | 4159 |
| Wala | 4270 |

