


15-151-22206

9-26s-11w



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Raymond Oil**

PO Box 48798
Wichita KS 67201-8788

ATTN: Rocky Milford

Sec-9 Twp-26s Rge-11

Bauman #1

Start Date: 2004.09.25 @ 06:35:17

End Date: 2004.09.25 @ 14:41:47

Job Ticket #: 18343 DST #: 1

API 15-151-22206-00-00

NE SW SW

1000 FSL 1010 FWL

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620

Raymond Oil


Bauman #1

Sec-9 Twp-26s Rge-11

DST # 1

Toronto

2004.09.25



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

Raymond Oil
PO Box 48798
Wichita KS 67201-8788

ATTN: Rocky Milford

Bauman #1

Sec-9 Twp-26s Rge-11

Job Ticket: 18343

DST#: 1

Test Start: 2004.09.25 @ 06:35:17

GENERAL INFORMATION:

Formation: **Toronto**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 09:11:17

Time Test Ended: 14:41:47

Test Type: Conventional Bottom Hole

Tester: Steve Clark

Unit No: 19

Interval: **3416.00 ft (KB) To 3448.00 ft (KB) (TVD)**

Total Depth: **3448.00 ft (KB) (TVD)**

Hole Diameter: **7.83 inches** Hole Condition: Fair

Reference Elevations: **1856.00 ft (KB)**

1847.00 ft (CF)

KB to GR/CF: **9.00 ft**

Serial #: 6667

Inside

Press@RunDepth: **70.64 psig @ 3418.00 ft (KB)**

Start Date: **2004.09.25**

End Date:

2004.09.25

Start Time: **06:35:27**

End Time:

14:41:47


Capacity: **7000.00 psig**

Last Calib.: **2004.09.25**

Time On Btm: **2004.09.25 @ 09:10:32**

Time Off Btm: **2004.09.25 @ 12:41:17**

TEST COMMENT: IF-w k-5in blw 30min
ISI-After bleed off no blw
FF-w k-41/4in blw 45min
FSI-After bleed off no blw



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1753.65	108.32	Initial Hydro-static
1	22.63	108.06	Open To Flow (1)
30	39.93	109.25	Shut-In (1)
86	1252.51	110.91	End Shut-In (1)
89	42.42	110.53	Open To Flow (2)
133	70.64	111.71	Shut-In (2)
209	1216.22	112.44	End Shut-In (2)
211	1671.58	112.66	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
60.00	80% mud 20% water	0.84
45.00	100% mud	0.63

Gas Rates

Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raymond Oil

Bauman #1

PO Box 48798
Wichita KS 67201-8788

Sec-9 Twp-26s Rge-11

Job Ticket: 18343

DST#: 1

ATTN: Rocky Milford


Test Start: 2004.09.25 @ 06:35:17

Tool Information

Drill Pipe:	Length:	3409.00 ft	Diameter:	3.80 inches	Volume:	47.82 bbl	Tool Weight:	2500.00 lb	
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	2.70 inches	Volume:	0.00 bbl	Weight set on Packer:	25000.00 lb	
Drill Collar:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight to Pull Loose:	63000.00 lb	
						Total Volume:	47.82 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	22.00 ft							String Weight: Initial	59000.00 lb
Depth to Top Packer:	3416.00 ft							Final	62000.00 lb
Depth to Bottom Packer:	ft								
Interval between Packers:	32.00 ft								
Tool Length:	61.00 ft								
Number of Packers:	2	Diameter:	6.75 inches						
Tool Comments:									

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3388.00	
Shut In Tool	5.00			3393.00	
Hydraulic tool	5.00			3398.00	
Jars	5.00			3403.00	
Safety Joint	3.00			3406.00	
Packer	5.00			3411.00	29.00 Bottom Of Top Packer
Packer	5.00			3416.00	
Perforations	2.00			3418.00	
Recorder	0.00	6667	Inside	3418.00	
Perforations	27.00			3445.00	
Recorder	0.00	11019	Outside	3445.00	
Bullnose	3.00			3448.00	32.00 Bottom Packers & Anchor

Total Tool Length: 61.00



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

FLUID SUMMARY

Raymond Oil

Bauman #1

PO Box 48798
Wichita KS 67201-8788

Sec-9 Twp-26s Rge-11

Job Ticket: 18343

DST#: 1

ATTN: Rocky Milford

Test Start: 2004.09.25 @ 06:35:17

Mud and Cushion Information

Mud Type: Gel Chem

Mud Weight: 9.00 lb/gal

Viscosity: 46.00 sec/qt

Water Loss: 10.34 in³

Resistivity: ohm.m

Salinity: 5000.00 ppm

Filter Cake: inches

Cushion Type:

Cushion Length: ft

Cushion Volume: bbl

Gas Cushion Type:

Gas Cushion Pressure: psig

Oil API: deg API

Water Salinity: 2400 ppm

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
60.00	80% mud 20% w water	0.842
45.00	100% mud	0.631

Total Length: 105.00 ft Total Volume: 1.473 bbl

Num Fluid Samples: 2


Num Gas Bombs: 0


Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: No gas detected





DRILL STEM TEST REPORT

Prepared For: **Raymond Oil**
PO Box 48798
Wichita KS 67201-8788

ATTN: Rocky Milford

Sec-9 Twp-26s Rge-11

Bauman #1

Start Date: 2004.09.26 @ 00:00:00
End Date: 2004.09.26 @ 07:00:00
Job Ticket #: 18344 DST #: 2

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

Raymond Oil

Bauman #1

Sec-9 Twp-26s Rge-11

DST # 2

Lower Kansas City

2004.09.26



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

Raymond Oil
PO Box 48798
Wichita KS 67201-8788
ATTN: Rocky Milford

Bauman #1

Sec-9 Twp-26s Rge-11

Job Ticket: 18344

DST#: 2

Test Start: 2004.09.26 @ 00:00:00

GENERAL INFORMATION:

Formation: **Lower Kansas City**
Deviated: **No** Whipstock: **ft (KB)**
Time Tool Opened: 05:04:02
Time Test Ended: 07:00:00
Interval: **3609.00 ft (KB) To 3642.00 ft (KB) (TVD)**
Total Depth: **3642.00 ft (KB) (TVD)**
Hole Diameter: **7.83 inches** Hole Condition: **Fair**

Test Type: **Conventional Bottom Hole**
Tester: **Steve Clark**
Unit No: **19**

Reference Elevations: **1856.00 ft (KB)**
1847.00 ft (CF)
KB to GR/CF: **9.00 ft**

Serial #: 6667

Inside

Press@RunDepth: **34.23 psig @ 3611.00 ft (KB)**

Start Date: **2004.09.26**

End Date:

2004.09.26

Capacity: **7000.00 psig**

Start Time:

02:36:12

End Time:


09:25:02

Last Calib.: **2004.09.26**

Time On Btm: **2004.09.26 @ 05:03:17**

Time Off Btm: **2004.09.26 @ 07:15:17**

TEST COMMENT: IF-w k-3"strg blw 30min
ISL-after bleed off no blw
FF-w k-21 1/2"strg blw 30min
FSL-after bleed off no blw



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1840.43	107.83	Initial Hydro-static
1	19.22	107.48	Open To Flow (1)
27	28.00	107.67	Shut-In (1)
63	72.44	109.01	End Shut-In (1)
65	27.85	109.05	Open To Flow (2)
106	34.23	110.58	Shut-In (2)
130	77.73	111.35	End Shut-In (2)
133	1748.92	113.02	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
20.00	oil spec mud 6%oil-94%mud	0.28

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raymond Oil

Bauman #1

PO Box 48798
Wichita KS 67201-8788

Sec-9 Twp-26s Rge-11

Job Ticket: 18344

DST#: 2

ATTN: Rocky Milford

Test Start: 2004.09.26 @ 00:00:00

Tool Information

Drill Pipe: Length: 3595.00 ft Diameter: 3.80 inches Volume: 50.43 bbl
Heavy Wt. Pipe: Length: 0.00 ft Diameter: 2.70 inches Volume: 0.00 bbl
Drill Collar: Length: 0.00 ft Diameter: 2.25 inches Volume: 0.00 bbl
Total Volume: 50.43 bbl

Tool Weight: 2500.00 lb

Weight set on Packer: 25000.00 lb

Weight to Pull Loose: 63000.00 lb

Tool Chased 0.00 ft

String Weight: Initial 61000.00 lb

Final 61000.00 lb

Drill Pipe Above KB: 15.00 ft

Depth to Top Packer: 3609.00 ft

Depth to Bottom Packer: ft

Interval between Packers: 33.00 ft

Tool Length: 62.00 ft


Number of Packers: 2 Diameter: 6.75 inches

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
------------------	-------------	------------	----------	------------	----------------

Change Over Sub	1.00			3581.00	
Shut In Tool	5.00			3586.00	
Hydraulic tool	5.00			3591.00	
Jars	5.00			3596.00	
Safety Joint	3.00			3599.00	
Packer	5.00			3604.00	29.00 Bottom Of Top Packer
Packer	5.00			3609.00	
Perforations	2.00			3611.00	
Recorder	0.00	6667	Inside	3611.00	
Perforations	27.00			3638.00	
Recorder	0.00	11019	Outside	3638.00	
Perforations	1.00			3639.00	
Bullnose	3.00			3642.00	33.00 Bottom Packers & Anchor

Total Tool Length: 62.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Raymond Oil

Bauman #1

PO Box 48798
Wichita KS 67201-8788

Sec-9 Twp-26s Rge-11

Job Ticket: 18344

DST#: 2

ATTN: Rocky Milford

Test Start: 2004.09.26 @ 00:00:00

Mud and Cushion Information

Mud Type: Gel Chem

Mud Weight: 9.00 lb/gal

Viscosity: 45.00 sec/qt

Water Loss: 10.56 in³

Resistivity: ohm.m

Salinity: 6800.00 ppm

Filter Cake: inches

Cushion Type:

Cushion Length:

Cushion Volume:

Gas Cushion Type:

Gas Cushion Pressure:

ft

bbl

psig

Oil API:

Water Salinity:

deg API

ppm

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
20.00	oil spec mud 6%oil-94%mud	0.281

Total Length: 20.00 ft Total Volume: 0.281 bbl

Num Fluid Samples: 2

Num Gas Bombs: 0


Serial #:


Laboratory Name:

Laboratory Location:

Recovery Comments: slight odor of gas

Pressure vs. Time





DRILL STEM TEST REPORT

Prepared For: **Raymond Oil**

PO Box 48798
Wichita KS 67201-8788

ATTN: Rocky Milford

Sec-9 Twp-26s Rge-11

Bauman #1


Start Date: 2004.09.26 @ 16:49:50

End Date: 2004.09.26 @ 22:26:05

Job Ticket #: 18345

DST #: 3

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Raymond Oil
PO Box 48798
Wichita KS 67201-8788
ATTN: Rocky Milford

Bauman #1

Sec-9 Twp-26s Rge-11

Job Ticket: 18345

DST#: 3

Test Start: 2004.09.26 @ 16:49:50

GENERAL INFORMATION:

Formation: **Lansing**
Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 18:31:50

Time Test Ended: 22:26:05

Interval: **3643.00 ft (KB) To 3670.00 ft (KB) (TVD)**

Total Depth: **3670.00 ft (KB) (TVD)**

Hole Diameter: **7.83 inches** Hole Condition: **Fair**

Test Type: **Conventional Bottom Hole**

Tester: **Steve Clark**

Unit No: **19**

Reference Elevations: **1856.00 ft (KB)**

1847.00 ft (CF)

KB to GR/CF: **9.00 ft**

Serial #: 6667

Inside

Press@RunDepth: **23.36 psig @ 3643.00 ft (KB)**

Start Date: **2004.09.26**

End Date:

2004.09.26

Capacity: **7000.00 psig**

Last Calib.: **2004.09.26**

Start Time: **16:50:00**

End Time:


22:26:05

Time On Btm: **2004.09.26 @ 18:31:20**

Time Off Btm: **2004.09.26 @ 20:32:50**

TEST COMMENT: IF-no blw
IS-no blw
FF-no blw flushed tool had bble no blw
FS-no blw

Pressure vs. Time



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1765.98	106.27	Initial Hydro-static
1	21.37	106.24	Open To Flow (1)
29	21.66	106.42	Shut-In(1)
59	38.95	107.25	End Shut-In(1)
61	22.06	107.29	Open To Flow (2)
88	23.36	109.22	Shut-In(2)
121	48.69	109.94	End Shut-In(2)
122	1715.37	110.48	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
15.00	lightly oil spec mud 1%oil-99%mud	0.21

Gas Rates

Choke (Inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raymond Oil

Bauman #1

PO Box 48798
Wichita KS 67201-8788

Sec-9 Twp-26s Rge-11

ATTN: Rocky Milford

Job Ticket: 18345

DST#: 3

Test Start: 2004.09.26 @ 16:49:50

Tool Information

Drill Pipe:	Length: 3635.00 ft	Diameter: 3.80 inches	Volume: 50.99 bbl
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 2.70 inches	Volume: 0.00 bbl
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl
			Total Volume: 50.99 bbl

Tool Weight:	2500.00 lb
Weight set on Packer:	25000.00 lb
Weight to Pull Loose:	68000.00 lb
Tool Chased	0.00 ft
String Weight: Initial	64000.00 lb
Final	64000.00 lb

Drill Pipe Above KB: 20.00 ft
Depth to Top Packer: 3643.00 ft
Depth to Bottom Packer: ft
Interval between Packers: 27.00 ft
Tool Length: 55.00 ft
Number of Packers: 2 Diameter: 6.75 inches

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Shut In Tool	5.00			3620.00	
Hydraulic tool	5.00			3625.00	
Jars	5.00			3630.00	
Safety Joint	3.00			3633.00	
Packer	5.00			3638.00	28.00 Bottom Of Top Packer
Packer	5.00			3643.00	
Recorder	0.00	6667	Inside	3643.00	
Perforations	24.00			3667.00	
Recorder	0.00	11019	Outside	3667.00	
Bullnose	3.00			3670.00	27.00 Bottom Packers & Anchor
Total Tool Length:		55.00			



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

FLUID SUMMARY

Raymond Oil

Bauman #1

PO Box 48798
Wichita KS 67201-8788

Sec-9 Twp-26s Rge-11

Job Ticket: 18345

DST#: 3

ATTN: Rocky Milford

Test Start: 2004.09.26 @ 16:49:50

Mud and Cushion Information

Mud Type: Gel Chem

Mud Weight: 9.00 lb/gal

Viscosity: 46.00 sec/qt

Water Loss: 8.78 in³

Resistivity: ohm.m

Salinity: 8000.00 ppm

Filter Cake: inches

Cushion Type:

Cushion Length:

Cushion Volume:

Gas Cushion Type:

Gas Cushion Pressure:

ft

bbl

psig

Oil API:

Water Salinity:

deg API

ppm

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
15.00	lightly oil spec mud 1%oil-99%mud	0.210

Total Length: 15.00 ft

Total Volume: 0.210 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:


Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time





TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Raymond Oil**

PO Box 48798
Wichita KS 67201-8788

ATTN: Rocky Milford

Sec-9 Twp-26s Rge-11

Bauman #1


Start Date: 2004.09.29 @ 04:50:48

End Date: 2004.09.29 @ 12:27:48

Job Ticket #: 19771

DST #: 4

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Raymond Oil

PO Box 48798
Wichita KS 67201-8788

ATTN: Rocky Milford

Bauman #1

Sec-9 Twp-26s Rge-11

Job Ticket: 19771

DST#: 4

Test Start: 2004.09.29 @ 04:50:48

GENERAL INFORMATION:

Formation: Viola

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 07:09:48

Time Test Ended: 12:27:48

Test Type: Conventional Straddle

Tester: Gary Pevoteaux

Unit No: 23

Interval: 4126.00 ft (KB) To 4261.00 ft (KB) (TVD)

Total Depth: 4313.00 ft (KB) (TVD)

Hole Diameter: 7.83 inches Hole Condition: Poor

Reference Elevations: 1856.00 ft (KB)

1847.00 ft (CF)

KB to GR/CF: 9.00 ft

Serial #: 6755

Inside

Press@RunDepth: 413.13 psig @ 4127.00 ft (KB)

Start Date: 2004.09.29

End Date:

2004.09.29

Start Time: 04:50:53

End Time:

12:27:47

Capacity: 7000.00 psig

Last Calib.: 2004.09.29

Time On Btm: 2004.09.29 @ 07:08:03


Time Off Btm: 2004.09.29 @ 09:25:18

TEST COMMENT: IF: Strong blow . B.O.B. in 8 mins.

IS: No blow .

FF: Fair to strong blow . B.O.B. in 13 mins.

FS: No blow .



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2138.18	119.42	Initial Hydro-static
2	28.01	118.76	Open To Flow (1)
40	292.11	123.55	Shut-In(1)
72	894.59	125.91	End Shut-In(1)
72	289.99	125.74	Open To Flow (2)
101	413.13	127.55	Shut-In(2)
136	894.60	128.16	End Shut-In(2)
138	2113.28	128.51	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
317.00	SW Rw .09 ohms @ 73 deg.	4.45
250.00	MW 46%w 54%w	3.51
345.00	Drig.mud	4.84

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raymond Oil

Bauman #1

PO Box 48798
Wichita KS 67201-8788

Sec-9 Twp-26s Rge-11

Job Ticket: 19771

DST#: 4

ATTN: Rocky Milford

Test Start: 2004.09.29 @ 04:50:48

Tool Information

Drill Pipe:	Length: 4131.00 ft	Diameter: 3.80 inches	Volume: 57.95 bbl
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl
			Total Volume: 57.95 bbl

Tool Weight:	2100.00 lb
Weight set on Packer:	20000.00 lb
Weight to Pull Loose:	90000.00 lb
Tool Chased	0.00 ft
String Weight: Initial	71000.00 lb
Final	73000.00 lb

Drill Pipe Above KB: 27.00 ft
Depth to Top Packer: 4126.00 ft
Depth to Bottom Packer: 4261.00 ft
Interval between Packers: 135.00 ft
Tool Length: 209.00 ft

Number of Packers: 3 Diameter: 6.75 inches

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			4105.00	
Shut In Tool	5.00			4110.00	
Hydraulic tool	5.00			4115.00	
Safety Joint	2.00			4117.00	
Packer	4.00			4121.00	22.00 Bottom Of Top Packer
Packer	5.00			4126.00	
Stubb	1.00			4127.00	
Recorder	0.00	6755	Inside	4127.00	
Perforations	3.00			4130.00	
Change Over Sub	1.00			4131.00	
Blank Spacing	125.00			4256.00	
Recorder	0.00	10290	Outside	4256.00	
Change Over Sub	1.00			4257.00	
Blank Off Sub	1.00			4258.00	
travel collar	3.00			4261.00	135.00 Tool Interval
Packer	0.00			4261.00	
Stubb	1.00			4262.00	
Perforations	13.00			4275.00	
Change Over Sub	1.00			4276.00	
Blank Spacing	31.00			4307.00	
Change Over Sub	1.00			4308.00	
Recorder	0.00	13222	Below	4308.00	
Bullnose	5.00			4313.00	52.00 Bottom Packers & Anchor
Total Tool Length:		209.00			



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Raymond Oil

Bauman #1

PO Box 48798
Wichita KS 67201-8788

Sec-9 Twp-26s Rge-11

Job Ticket: 19771

DST#:4

ATTN: Rocky Milford

Test Start: 2004.09.29 @ 04:50:48

Mud and Cushion Information

Mud Type: Gel Chem

Mud Weight: 10.00 lb/gal

Viscosity: 50.00 sec/qt

Water Loss: 10.19 in³

Resistivity: 0.00 ohm.m

Salinity: 7000.00 ppm

Filter Cake: 0.20 inches

Cushion Type:

Cushion Length:

Cushion Volume:

Gas Cushion Type:

Gas Cushion Pressure:

ft

bbl

psig

Oil API:

deg API

Water Salinity: 86000 ppm

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
317.00	SW Rw .09 ohms @ 73 deg.	4.447
250.00	MMV 46%w 54%w	3.507
345.00	Drlg.mud	4.839

Total Length: 912.00 ft

Total Volume: 12.793 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #: none

Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time



233973