


7-26-11W

LION OIL REFG.CO.  
 Moeller No. 2.

SEC.7 T.26 R.11 W  
 CSW SW

Total Depth. 4153'  
 Comm. 6-8-43 Comp. 7-3-43  
 Shot or Treated.  
 Contractor. R.W.Rine Drlg.Co.  
 Issued. 8-7-43

County. Pratt



CASING:  
 8 5/8" 300' Cem.  
 5 1/2" 4150'

Elevation.

Production. Pot.3000 B.

Figures Indicate Bottom of Formations.

clay & sand	top -90
sand	120
sand & shale	220
red bed	300
red bed & shale	650
shale & shells	1695
lime	1720
lime brkn	1810
lime	1970
shale	1980
lime	2020
shale & shells	2051
sand & shale	2135
shale	2270
lime	2410
lime brkn	2485
shale	2760
shale & shells	2820
lime	2950
shale	3085
lime	3215
shale	3225
lime	3245
lime & shale brks	3330
lime	3455
shale	3465
lime	3604
lime & shale	3680
lime	3739
lime & chert	3777
lime	3970
chert	4027
chert & shale	4048
shale	4149
lime	4153
Total Depth.	

Tops: Kansas City Lime 3616 DF  
 Viola Lime 4147 DF

Drill stem test at 4153  
 650' oil in 15 min.

