

1626-11W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- NATURAL GAS & OIL CORP.
 Farm- Shrivor No. 1

SEC. 16 T. 26
 SW SE NW

R.11W

County Pratt

KANSAS



Total Depth 4463'

Comm. 4-21-54

Comp. 5-8-54

Shot or Treated.

Contractor. Drlg. Department of Natural Gas & Oil Corp.

Issued. 6-19-54

CASING:

10 3/4" 385' w/325 sx com.

Elevation. 1841' RB

Production. Dry

Figures indicate Bottom of Formations.

collar	90	1 hr., SI 20 min, weak blow
sand	110	50 min, rec. 60' gas, 45' sl
red sand rock	310	oil & gas out mud, no pros-
red bed-shells	335	sures recorded.
red shalo-shells	405	
red bed w/sand		#2- 3714-42, open 1 hr, SI
stks	600	20 min, fair blow throat
Anhydrito	627	Rec. 242' sl oil & gas cut
shalo-shells	1170	muddy wtr, IFP 120#, FFP 170#.
salt-shalo	1390	BHP 1320#.
shab-limo	1475	
shalo-shells	1550	#3- 3764-3800, open 1 hr. SI
limo-shalo	1730	20 min, weak blow 30 min,
limo	1950	rec. 30' sl oil cut mud, no
limo-shalo	3135	IFP or FFP, 135# BHP.
limo	3425	
shalo-limo	3487	#4- 4335-73, open 1 hr, SI
sand	3529	20 min, weak blow 5 min, rec.
shalo-limo	3565	10' mud, no IFP or FFP, 175#
shalo	3590	BHP.
limo	3880	
limo-shalo stks	3917	Schlumberger run.
limo	3951	
limo-shalo	3999	
cherty limo	4047	
chert	4092	
limo-shalo	4115	
limo	4132	
shalo	4155	
shab-limo	4208	
shalo	4248	
chert	4255	
limo-chert	4309	
limo	4336	
Simpson shalo-		
sand	4373	
shalo	4409	
Arbucklo limo	4420	
limo-chert-		
Pyrito	4449	
limo	4463	
Total Depth		

TOPS:

Anhydrito	600
Heobner	3414
Douglas	3496
Brown Limo	3591
Lansing	3604
Cherty Conglom-	
orato	4015
Mississippi	4038
Kinderhook	4130
Viola	4245
Simpson	4336
Arbucklo	4409

DRILL STEM TESTS:

#1- 3672-3708, open