

KANSAS

**WELL COMPLETION REPORT AND DRILLER'S LOG**

This is an OWWO; initial drilling done by Natural Gas & Oil Corp. May 7/8, 1954.

S. 16 T. 26S R. 11 <sup>KX</sup> W  
 State Geological Survey  
 Loc. WICHITA BRANCH  
 County PRATT

Operator  
J. A. ALLISON

Address  
300 W. Douglas, Suite 305, Wichita, KS 67202


Well No. 2 Lease Name Shriver OWWO

Footage Location  
 feet from (N) (S) line \_\_\_\_\_ feet from (E) (W) line \_\_\_\_\_

Principal Contractor DNB Drilling Company Geologist \_\_\_\_\_

Spud Date 4/12/80 Date Completed 6/27/80 Total Depth 4340' P.B.T.D. \_\_\_\_\_

Directional Deviation \_\_\_\_\_ Oil and/or Gas Purchaser \_\_\_\_\_



640 Acres  
 N  
 Locate well correctly  
 Elev.: Gr. 1837  
 DF 1839 KB 1841

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Oil String	7-7/8	5-1/2	14	4146	60/40pozmix	150	10% salt Sat.

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	DP's	4041-50
<b>TUBING RECORD</b>			4	DP's	3897-3900
			4	DP's	3866-3871
Size	Setting depth	Packer set at	4	DP's	3773-3778
2- 7/8 EUE	3797	3797			3614-3618

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
1000 gl. acid and 10,000 lbs. sand frac.	4041-4051
Communicated with Mississippian	3897-3900
	3866-3871
500 gl. MCA	3773-3778
	3614-3618

**INITIAL PRODUCTION**

Date of first production August 31, 1980 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil <u>20</u> bbls.	Gas <u>1</u> MMP si	Water <u>50</u> bbls.	Gas-oil ratio
		MCF		CFPB

Disposition of gas (vented, used on lease or sold) Shut in for pipe line connection Producing interval(s) 3773-3778 3614-3618

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

ator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

J. A. ALLISON

Oil

Well No.

2

Lease Name

SHRIVER OWWO

S 16 T 26 S R 11 <sup>EX</sup> W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

6/11/80 Panhandle Eastern tested  
Mississippian gas SIP 1234#.  
Open flow 1046 MCFG/D.

Perforations 3897'-3900',  
3866'-3871' communicated with Miss-  
issippian perms.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*J. A. Allison*  
Signature

OWNER

Title

October 10, 1980

Date