

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

Plotted

LM.

18-26-11W

GEORGE E. REEVES.  
Stark No. 1.

SEC. 18 T. 26 R. 11W.  
CWL SW NW

DISCOVERY WELL.

Total Depth. 4339 P.B. 4154  
Comm. 3-16-41 Comp. 4-30-41  
Shot or Treated. 1000 Gals. Acid  
Contractor. Pulse Drilling Co., Inc.,  
Issued. 5-10-41

County Pratt.



CASING.

103/4" 261' cemented.  
4 1/2" 4123' cemented.

Elevation.

Production. 12,000,000 G.

Figures Indicate Bottom of Formations.

|                      |      |
|----------------------|------|
| surface and sand     | 165  |
| shale                | 180  |
| sand and gravel      | 240  |
| red bed and gravel   | 311  |
| red bed              | 335  |
| red rock             | 640  |
| anhydrite            | 655  |
| shale and shells     | 1350 |
| broken lime          | 1560 |
| lime                 | 1840 |
| broken lime          | 1890 |
| lime                 | 2125 |
| shale                | 2130 |
| broken lime          | 2215 |
| lime                 | 2640 |
| shale and shells     | 2730 |
| broken lime          | 2835 |
| shale                | 2900 |
| lime                 | 2980 |
| broken lime          | 3120 |
| lime                 | 3415 |
| broken lime          | 3535 |
| lime                 | 3567 |
| broken lime          | 3600 |
| lime                 | 3871 |
| broken lime          | 3928 |
| lime                 | 3968 |
| shale                | 3984 |
| lime                 | 4001 |
| chert                | 4016 |
| shale                | 4085 |
| shale and shells     | 4121 |
| lime Viola           | 4152 |
| Viola chert          | 4164 |
| lime                 | 4208 |
| sand with shale brks | 4251 |
| shale                | 4291 |
| Arbuckle lime        | 4339 |
| Total Depth.         |      |

P.B. and cemented 4154.

The well was completed in the Viola  
from 4121 to 4152, as a 12M ft gas well.

Tops: Lansing 3600  
Viola 4121  
Simpson 4211  
Arbuckle 4289