

18-26-11W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY A. D. ALLISON ET AL

SEC. 18 T. 26 R. 11W

FARM Stark

NO. 1

LOC. C S¹/₂ SW NW
660' fr WL & 330' fr SL of NW/4

TOTAL DEPTH 4288

COMM. 12-8-50


COMP. 1-3-51

COUNTY Pratt

SHOT OR TREATED

CONTRACTOR A. D. Allison & Co., Inc.

ISSUED 1-20-51



CASING

8 5/8" 330'

ELEVATION 186 L/m
186 3 RB Ind.

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

clay	35
sand & shale	160
sand & shells	205
redbed & shells	275
sand	280
shale & shells	375
redbed & shells	690
shale & shells	800
shale, shells & salt	945
shale & lime	1186
shale & shells	1500
shale & lime	2045
lime	2310
lime & shale	2400
lime	2594
lime & shale	3110
lime	3430
lime & shale	3615
lime	3960
lime & shale	4025
lime & chert	4077
lime	4097
lime & chert	4120
lime	4288
Total depth	

Tops:

Heebner	3408
Toronto	3425
Douglas	3442
Brown lime	3584
Lansing-Kansas City	3606
Conglomerate	3992
Viola	4055
Simpson sand	4154
Arbuckle	4228