

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


18-26-11W

Company - ATLANTIC REFG. CO.
Farm - Stark No. 1.

SEC. 18 T. 26 R. 11 W
CNE NW
140'W CNE NW

Total Depth. 4204=4201 Corr.
Comm. 10-7-43 Comp. 12-18-43
Shot or Treated.
Contractor. Heimerich & Payne, Inc.
Issued. 2-5-44

County. Pratt
KANSAS



CASING:
10 3/4" 386' Cem.
7" 4196' Cem.

Elevation. _____

Production. Pot. 189 B.

Figures Indicate Bottom of Formations.

surface clay	0-40	shale	4121
sand & gravel	163	lime & shale	4139
shale & shells	411	lime brkn & shale	4151
sand & shale	559	lime	4168
shale & shells	1220	shale	4192
salt & shale	1550	shale & Viola lime	4204=01
shale & brkn lime	1620	Total Depth.	Corr.
lime brkn	1840		
sdv lime hd	1880		
shale	1930	Tops:	
shale & shells	1978	Lansing	3619
shale	2030	Conglomerate	4005
shale & shells	2105	Miss.	4023
lime brkn & shale	2164	Kinderhook	4072
shale & lime shells	2228	Viola	4194=4191 Corr.
lime	2318		
lime & shale	2360		
lime	2395		
lime brkn & shale	2535		
lime	2585		
lime & shale	2610		
lime sdv	2618		
lime	2641		
lime brkn, shells, shale	2685	lime sdv	3738
shale	2701	lime	3777
lime	2768	lime hd	3780
shale & brkn lime	2839	lime	3893
lime	2865	lime brkn w/shale	4002
lime hd & shale	2995	lime hd, shale	4015
shale	3008	lime hd, chert	4026
shale & lime	3137	lime, shale, chert	4030
lime	3340	chert	4036
lime hd	3352	lime, shale, chert	4045
lime	3438	chert	4052
lime hd	3447	chert & lime	4062
lime	3494	shale, lime, chert	4069
lime sdv	3514	chert	4073
lime & shale	3554	chert & lime	4081
lime hd	3588	lime, shale, chert	4092
shale	3602		
shale & lime	3680		
lime	3721		