

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock, Wichita, Kansas

Company - SKELLY OIL COMPANY  
Farm - J. G. Schlenz No. 1

SEC. 6 T. 26 R. 11W  
SE SE SW  
330' FEL, 330' FSL SW  $\frac{1}{4}$

Total Depth. 4338  
Comm. 8-22-50 Comp. 9-15-50  
Shot or Treated.  
Contractor. Chas. Hulme Drilling Co  
Issued. 10-14-50

County. Pratt  
KANSAS



CASING:  
8 5/8" 433' cem w/250 sx.

Elevation. 1856 DF

Production. Dry

Figures indicate Bottom of Formations.

surface soil, sand 170  
red bed 350  
shale, shells 433  
Drilled 13 1/4" hole  
shale, shells 1180  
salt 1300  
lime, shale 1680  
lime sdy. 1750  
lime 1830  
lime, shale 1910  
lime 2000  
lime, shale 2585  
shale, shells 2800  
shale 2850  
lime, shale 3010  
lime 3140  
lime, shale 3180  
lime 3425  
lime sdy 3520  
lime sdy, shale 3583  
lime, shale 3624  
lime 3639  
lime slightly porous 3644  
lime 3654  
lime slightly porous 3656  
lime 3759  
lime gry fine xlyn  
oolicastic 3762  
lime 3787  
lime slightly porous 3792  
lime 3979  
chert 4005  
chert, shale 4012  
lime, chert 4025  
lime 4049  
lime, shale 4120  
lime, chert 4133  
chert gry weathered  
slightly porous 4136  
dolo., dense chert and  
cherty slightly porous  
4150  
dolo., gry slightly  
porous cherty 4158  
dolo., gry fine granular  
to fine xlyn slightly  
porous 4165  
lime, chert 4224  
lime 4242  
lime sdy 4275  
shale 4297  
shale, sand 4313  
dolomite gry 4338  
Total depth

Tops: Continued  
Viola line 4133  
Simpson sand 4230  
Arbuckle lime 4313

DST 4136-50, packer set at 4135',  
open 50 mins, rec. 90' rotary mud  
no oil or gas.  
DST 4158-65, packer set at 4154',  
open 1 hr, rec. 70' rotary mud  
and water w/very slight rainbow  
show of oil.

Tops:  
Heebner shale 3406  
Lansing lime 3611  
Mississippi lime 3975  
Kinderhook shale 4104