

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

GEORGE E. REEVES.
Stark No. 1.

SEC. 18 T. 26 R. 11W.
CWL SW NW

DISCOVERY WELL.

Total Depth. 4339 P.B. 4154
Comm. 3-16-41 Comp. 4-30-41
Shot or Treated. 1000 Gals. Acid
Contractor. Pulse Drilling Co., Inc.,
Issued. 5-10-41

County Pratt.



CASING.

103/4" 261' cemented.
4 1/2" 4123' cemented.

Elevation.

Production. 12,000,000 G.

Figures Indicate Bottom of Formations.

surface and sand	165
shale	180
sand and gravel	240
red bed and gravel	311
red bed	335
red rock	640
anhydrite	655
shale and shells	1350
broken lime	1560
lime	1840
broken lime	1890
lime	2125
shale	2130
broken lime	2215
lime	2640
shale and shells	2730
broken lime	2835
shale	2900
lime	2980
broken lime	3120
lime	3415
broken lime	3535
lime	3567
broken lime	3600
lime	3871
broken lime	3926
lime	3968
shale	3984
lime	4001
chert	4016
shale	4085
shale and shells	4121
lime Viola	4152
Viola chert	4164
lime	4208
sand with shale brks	4251
shale	4291
Arbuckle lime	4339
Total Depth.	

P.B. and cemented 4154.

The well was completed in the Viola
from 4121 to 4152, as a 12M ft gas well.

Tops: Lansing 3600
Viola 4121
Simpson 4211
Arbuckle 4289