

126-12W  
CNE SE

AUG 15 1970

DRILLERS LOG

COMPANY:  
CONTRACTOR:  
LEASE NAME:  
LOCATION:  
  
ELEVATION:  
SURFACE CASING:  
COMMENCED:  
COMPLETED:  
ROTARY TOTAL DEPTH:

Leben Drilling, Inc.  
Aspen Drilling Co.  
Hoskinson #3  
150' So. of NE SE  
Sec. 1-T26S-R12W  
Pratt County, Kansas  
1875' KB  
12 jts. (234') 8 5/8"  
2-13-69  
2-24-69  
4230'

*Dry/viala*

| <u>FORMATION</u>    | <u>DEPTH</u> |
|---------------------|--------------|
| Shale & Sand        | 234          |
| Shale-Red Bed-Sand  | 580          |
| Shale & Shells      | 858          |
| Anhydrite           | 903          |
| Shale               | 1700         |
| Lime & Shale        | 1800         |
| Shale & Lime        | 1914         |
| Lime & shale        | 2310         |
| Shale & Lime        | 2485         |
| Shale               | 3170         |
| Shale & Chalky Lime | 3470         |
| Shale & Lime        | 3665         |
| Lime & Shale        | 3705         |
| Lime                | 4190         |
| Lime & Shale        | 4230         |
| RTD                 | 4230         |

Ran 12 jts. (234') 8 5/8"  
cemented with 260 sacks at  
232'.

DST #1, 4005-4025'

Ran electric log.

D & A

|                    |      |
|--------------------|------|
| <i>Helmer</i>      | 3432 |
| <i>Douglas</i>     | 3466 |
| <i>Bl. Line</i>    | 3614 |
| <i>LKC</i>         | 3640 |
| <i>BKC</i>         | 3964 |
| <i>Corp.</i>       | 4008 |
| <i>Ero. Miss</i>   | 4033 |
| <i>Miss Lm.</i>    | 4068 |
| <i>Kindershoat</i> | 4124 |
| <i>viala chat</i>  | 4190 |



AFFIDAVIT