

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


426 22W

Company- COPPINGER DRILLING, INC.
Farm- Snyder No. 1

SEC. 4 T. 26 R. 12W
NE NW SE

Total Depth. 4307
Comm. 8-27-55 Comp. 9-14-55
Shot or Treated.
Contractor. Coppinger Drilling, Inc.
Issued. 10-22-55

County Pratt KANSAS



CASING:

8 5/8 @ 326' w/ 175 sx cmt.

Elevation. 1878 DF

Production. Dry

Figures indicate Bottom of Formations.

sand	200
red bed & sand	290
red bed & shale	590
red bed	660
anhydrite	680
shale & shells	1185
salt & shale	1250
shale & shells	1470
lime & shale	2825
shale	2850
lime	2920
lime & shale	3275
lime	3450
lime & shale	3470
shale & sand	3552
shale	3610
lime & shale	3680
lime	3730
lime & shale	3780
lime	3860
lime & shale	3910
lime	3985
lime & shale	4049
cherty lime & shale	4065
lime	4090
shale	4100
chert	4138
lime & shale	4150
cherty lime & shale	4210
shale & sand	4255
lime & shale	4285
lime	4307
Total Depth	

TOPS:	SAMPLE	HALLIBURTON
Heebner	3436	3436
Toronto	3453	3448
Douglas	3469	3468
Brown lime	3612	3612
Lansing	3635	3635
Base K. C.	3950	3950
Marmaton	3966	3966
Mississippi	4049	4047
(conglomerate chert)		
Kinderhook	4065	4062
Viola*	4100	4118
Simpson*	4180	4198
Arbuckle	4282	4288

*Viola & Simpson tops have been re-correlated and the Halliburton log tops correspond with the more commonly called tops in this area and are thought to be correct.