

13-26-12W


KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY C. U. BAY
FARM Swertfeger NO. 1

SEC. 13 T. 26 R. 12W
LOC. SE SE SW

TOTAL DEPTH 4350
COMM. 9-29-50 COMP. 10-15-50
SHOT OR TREATED
CONTRACTOR Pickrell Drilling Co.
ISSUED 11-25-50

COUNTY Pratt
KANSAS



CASINO

8 5/8" 358' cem w/200 sx.

ELEVATION

PRODUCTION dry

Measurements from top rotary
ushing.

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar	5
sand	165
red bed	880
shale, salt	1590
shale, shells	1750
lime shale	1950
lime	2045
lime, shale	2210
lime	2325
lime, shale	2840
lime	2925
lime, shale	3075
lime	3330
lime, shale	3405
lime	3409
lime, shale	3605
lime	4010
lime, chert	4034
lime	4057
lime, shale	4077
lime	4290
lime, shale	4312
lime	4350
Total depth	

Tops:

Lansing	3600
Viola	4133
Simpson	4238
Arbuckle	4322

Filled hole w/heavy mud from 4350-350'
spotted 20 sx cement and mudded to 30'.
filled w/10 sx. cement to bottom of cellar.

DST 3792-3818, open 20" rec. 65' mud w/slight
show gas. BHP 1260#.
DST 3871-88, open 45", rec. 60' oil and gas cut
mud. BHP 590#.
DST 4135-47, open 45", rec. 15' sli. gas cut mud.
BHP 160#.