

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

19-26-12W

Company J.M. HUBER CORP.

Farm - Hoener

No. 1

SEC. 19

T. 26

R. 12 W

C SE SE

70' SE of CSE SE

Total Depth. 4320'

Comm. 5-7-44

Comp. 6-10-44

Shot or Treated.


Contractor. J.M. Huber Corp.

Issued. 7-29-44

County.

Pratt

KANSAS



CASING:

10 3/4"

485' Cem.

5 1/2"

4307' Cem.

Elevation. _____

Production. Phy. Pot. 58 B.

Figures Indicate Bottom of Formations.

surface soil	30	Tops:	
sand & gravel	190	Topeka	3174
red bed & sand strks	235	Heebner	3497
red bed & shells	485	Douglas	3534
shale	494	Brwn lime	3678
red bed & shells	750	Lansing	3696
anhydrite	785	3732-36 lime, low poro. lgt staining	
shale & shells	1085	3753-57 lime, low poro, fair staining	
shale shells & salt	1325	3796-05 lime, low poro, fair staining	
salt & shale	1655	3852-58 lime, good poro, good staining	
shale & lime	1933	3883-89 lime, fair pore, good staining	
lime	2000	3899-05 lime, low poro. fair staining	
lime & shale	2140	3944-50 lime, fair poro. lgt staining	
shale	2177	3977-82 lime, fair poro. lgt staining	
lime	2235	Base KC	3996
lime & shale	2308	Miss	4071
shale sticky	2320	Viola	4115
shale & lime	2470	4155-77 possible lgt stain in porous chert	
lime	2510	Simpson	4193
shale	2545	4227-31 sand, low porosity, lgt stain	
shale & lime	3139	Arbuckle	4305
lime sdy	3159		
lime	3180	Cored 3852-60 rec. 3'0"	
shale & lime	3219	0'6" lime, oolitic, porous saturated	
lime	3344	2'0" lime buff dense, thin shale partings	
lime brkn	3488	0'6" lime gy, fine xlyn, few spots, bleeding oil	
shale	3495	HDST 3876-91 open 30 min., rec. 65' oil & gas cut mud	
lime	3589	Cored 3897-3905 rec. 2'0"	
shale & sand	3622	2'0" lime, part oolitic, hd tight, bleeding	
sand & lime	3630		
lime & shale	3681		
lime	4022		
lime & shale	4063		
chert & lime	4187		
shale & lime	4220		
shale & sand	4239		
shale & lime	4266		
shale	4286		
shale & sand	4305		

T.D. Rotary 4305-4310 SLC

Drld plug & drld deeper to 4315

dolomite 4310-4315

sh oil 4312-55

filled up 500' oil in hole 12 hrs

dolomite (sh oil 4315-20) 4320

Total Depth.

Swbd 30 B0 22 hrs

Swbd 14 B0 12 hrs