

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


20-25

Company- NATIONAL COOPERATIVE REFINERY ASSOC. SEC. 20 T. 26 R. 12W  
Farm- Hoeme No. 3 NE SW SE

DEEPENING RECORD

Total Depth. 4336  
Comm. 1-16-52 Comp. 2-3-52  
Shot or Treated.  
Contractor. Transit Corp.  
Issued. 11-15-52

County Pratt KANSAS



Elevation. 1909 D.F.

Production. Dry

CASING:

8 5/8" 449' cem. w/300 sx.  
5 1/2" 4329 1/2" cem. w/150 sx.

Figures Indicate Bottom of Formations.

soil, sand, redbed & shale 380  
red bed & shells 815  
anhyd. 830  
red bed & shells 1330  
shale & shells 1585  
shells, shale 1665  
lime 1775  
lime sdy & shale 1940  
lime 2385  
lime & shale 2720  
shale, shells 2925  
lime, shale 3330  
lime 3400  
chalky lime 3500  
lime 3580  
lime, sand 3640  
shale 3650  
lime & shale 3843  
lime 4030  
lime & chert 4193  
lime 4216  
sand 4267  
lime 4285  
shale 4310  
Arb. lime 4330  
Total Depth

DEEPENING RECORD

Transit Corp.  
Comm. 8-20-52  
Comp. 10-1-52  
Prod. State pot. 125 bbls.  
OTD 4330  
Arb. lime 4336  
Total Depth

Tops:	Samples	Sch.
Anhyd.		722
Heebner	3488	3486
Toronto	3500	3502
Brown lime	3660	3685
Lansing	3685	3682
Mississippian	4046	4046
Viola lime	4074	4074
Simpson	4185	4200
Arbuckle	4310	4312

20' pen.

Cores: 4217-4267 pen. in Simpson  
D.S.T. 3794-3843 (109'-158') pen. in  
Lansing) open 2 hrs, fair blow 1 1/2 hrs, rec.  
210' SW., few drops oil, 150' gas, 1200#  
BHP

D.S.T. 3850-75 (1650190' pen. inLansing)  
open 1 hr. 40 mins., rec. 1500' gas.  
55' GCM., 300# BHP

D.S.T. 3911033 (226-251 pen. in Lansing)  
open 2 hrs, fair blow 1 hr., weak blow  
1 hr, rec. 55' GCM, 60' watery mud. 0#  
BHP

Schlumberger survey laterolog.