

29-26-12W

HOLLOW DRILG.CO., INC.  
 Hattie M. Brown "B" No. 1.

SEC. 29 T. 26 R. 12 W  
 SWc SE

DISCOVERY WELL

Total Depth. 4297½'  
 Comm. 10-23-42 Comp. 11-17-42  
 Shot or Treated.  
 Contractor, Hollow Drilg.Co., Inc.  
 Issued. 1-30-43

County. Pratt



CASING:

8" 467' Cem.  
 5½" 4267½' Cem.

Elevation.

Production. Pot. 3000 B.  
 No wtr

Figures Indicate Bottom of Formations.

cellar	0-10	coring Arbuckle	4281
surface sand & clay	70	Arbuckle	4293
sand	120	lime, oil pay-sw	
clay & shale	220	14 BPH 1900' off B.	4295½
red rock	708	lime, swb 18 BPH	
anhydrite	772	2300' off B.	4297½
red rock & shale	950	Total Depth.	
shale & shells	1010		
shale	1300		
salt	1475		
shale	1510		
salt & lime shells	1605		
shale & lime	1830		
lime	2040		
lime sdy	2078		
lime & shale	2092	12-12-42 Temp. Test,	
lime sdy	2185	swb 100 BPD	
lime & shale brks	2208	Acidized w/150 Gals.	
lime	2310	1-15-43	
shale & red rock	2335	Well flowed thru 2"	
lime	2400	tbg @ 38 BPH	
shale	2408	1-21-43 Pot. 6391 B.	
lime & shale	2470	indicated Pot. by Echo.,	
shale & lime shells	2594	State Pot. 3000 B.,	
lime & shale	2743	no wtr	
shale lime shells	2817		
shale	2850	Tops:	
lime	2940	Anhydrite	708
shale	2980	Ft. Riley	2050
lime	3007	B. Florence Flint	2190
shale & lime shells	3070	Topeka	3170
brkn lime & shale	3110	Heebner	3490
shale & red rock	3155	Lansing	3672
lime & shale	3170	Detrital Chert	4065
lime	3495	Viola	4109
shale	3525	Simpson Shale	4161
lime	3537	Arbuckle	4266
shale & lime shells	3580		
lime	3630		
shale	3690		
lime	3720		
lime & strks chert	3755		
lime	3800		
chert & lime	3810		
lime	3940		
shale	3945		
lime	3995		
shale	4043		
chert	4048		
shale & chert	4085		
lime	4099		
shale	4112		
chert	4143		
lime & shale	4185		
shale & sand	4192		
coring-no show	4196		
sand	4220		
shale	4241		
shale & sdy pyrite	4271		