


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

SHELL OIL CO., INC.
Ida Briggeman "A" No. 1.

SEC. 28 T. 26 R. 12 W
SW¹/₄ SW
330' S & W Lines SW¹/₄

Total Depth. 4314'
Comm. 4-29-43 Comp. 6-8-43
Shot or Treated.
Contractor.
Issued. 7-3-43

County. Pratt



CASING:
13" 42' Cem.
85/8" 1771' Cem.
4 1/2" 4270' Cem.

Elevation.

Production. DDD Pot. 24, 174 B.

Figures Indicate Bottom of Formations.

surface soil & sand	50	lime	4273
sand & shells	150	lime & shale	4293
sand & shale	255	4293 equals 4288 SLC	
sand & shells	287	dolomite	4314
red rock	460	Total Depth.	
red rock & shells	695		
shale, red rock, anhyd.	870		
shale & shells	1275	Tops:	
salt & shells	1330	Topeka	3168
salt, shale, shells	1515	Lansing	3677
shale, shells, anhydrite	1753	Viola	4095
anhydrite & lime	1771	Simpson	4172
lime & shale	2490	Arbuckle dolomite	4272
shale	2982		
lime & shale	3115	800' fluid	4288
shale	3155	4125' oil 37 1/2 hrs	4292
lime	3310	4200' oil 41 1/2 hrs	4295
shale	3380		
lime & shale	3451		
lime	3495		
lime & shale	3607		
3607 equals 3610 SLC			
shale	3630		
lime & shale	3704		
3704-16 lime, Core #1 no rec.			
lime	3730		
Core #2 rec. 30'			
10' shale green to blk			
20' lime, lgt oil stain			
lime	3741		
lime & shale	3771		
lime	3778		
Core #3 rec. 20'			
3' shale			
17' lime brown			
lime	3795		
lime & shale	3830		
Core #4 rec. 5'			
13" shale green			
21" lime ?			
6" lime			
9' lime, bleeding oil			
lime	3838		
lime & shale	3848		
Core #5 rec. 6'			
8" shale, 10" lime,			
44" lime			
lime	3880		
Core #6 rec. 7'			
7' lime, good stain			
lime	3921		
lime & shale	3973		
lime	4038		
lime & shale	4051		
lime & chert	4130		
shale, lime, chert	4172		
shale & sand	4216		
shale	4235		