


HOLLOW DRIG. CO., INC.  
Brown "B" No. 2.

SEC. 29 T. 26 R. 12 W  
SW SE SE

Total Depth. 4305'  
Comm. 3-3-43 Comp. 4-8-43  
Shot or Treated.  
Contractor.  
Issued. 7-17-43

County. Pratt



CASING:  
8 5/8" 474' Com.  
5 1/2" 4265 1/2' Com.

Elevation.

Production, Echo. Pot. 5674 B.

Figures Indicate Bottom of Formations.

cellar	0-10	dolomite, oil, hole	
shale & sand	90	filled from 2600' to	
gravel	150	3500', 3 hrs	4302 1/2
sand	255	dolomite sft, hole	
red rock-shale-sand	420	filled 1400' to 4305	
shale	450	in 3 hrs, flowing	
shells	468	thru 5 1/2"	4305
redrock	733	Total Depth.	
anhydrite	761		
shale	1053		
shale & shells	1275	Tops:	
salt	1550	Ft. Riley	2044
salt & shells	1700	Florence Flint	2169
lime	1983	Base Florence Flint	2189
lime & shale	2100	Topeka	3169
shale & shells	2135	Base Oread	3525
sdv shale	2165	"Brown" Lime	3652
shale & lime	2625	Lansing	3672
shale	2665	Marmaton Chert	4042
lime sdy	2685	Kinderhook Shale	4078
shale	2697	Viola	4095
shale & lime shells	2905	Simpson Shale	4154
shale	2990	Simpson Dolomite	4177
lime	3001	Simpson Sandstone	4189
shale & shells	3070	Arbuckle	4262
shale & lime	3165		
lime	3320	4-12-43 Pot. 5674 B.	
lime & shale	3385	indicated capacity, Echo.	
lime	3430		
shale	3445		
lime	3500		
sdv shale	3520		
lime & shale	3535		
lime brkn	3590		
lime	3625		
shale	3682		
lime	3933		
lime & shale	3964		
lime	4010		
shale	4050		
lime cherty	4071		
shale blk	4087		
shale	4098		
chert & lime	4153		
lime	4157		
shale & lime	4191		
sand	4195		
lime & shale	4214		
sand & shale	4247		
shale & lime	4266		
Arbuckle dolomite	4268		
dolomite	4273 1/2		
gas & oil show	4271-4273		
dolomite hd	4274 1/8		
dolomite sft	4279 1/2		
dolomite hd	4283		
dolomite med hd	4288		
dolomite hd	4295 1/2		