


SHELL OIL CO., INC.  
 C.Knop No. 1.

SEC.29 T.26 R.12 W  
 SWc NE  
 330'f SL 409'f WL NE $\frac{1}{2}$

County. Pratt

Total Depth. 4315'  
 Comm. 6-11-43 Comp. 7-13-43  
 Shot or Treated.  
 Contractor.  
 Issued. 8-21-43



CASING:  
 8 5/8" 791' Cem.  
 4 1/2" 4270' Cem.

Elevation.

Production. Pot. 3000 B.  
 (Ind. Cap. Echo. D.  
 60,070 B.)

Figures Indicate Bottom of Formations.

soil & shale	190
sand	239
red rock	296
red rock, lime strks	452
red rock, sand strks	602
red rock & sand	685
anhydrite	718
anhydrite & sand	762
anhydrite & red rock	802
red rock & shale	1058
shale & sand	1466
shale & lime	1794
anhydrite & shale	1874
shale & lime	2029
shale	2074
shale & lime	2190
lime	2321
shale & lime	2378
shale	2461
shale & lime	2596
shale	2678
shale & lime	3100
lime	3145
lime & sdy lime	3241
shale & lime	3286
lime	3348
shale & lime	3589
lime	3670
shale & lime	3838
lime	4005
lime & shale	4046
lime	4103
lime & chert	4183
lime	4234
lime & shale	4262
lime	4299
4299 equals 4295 SICorr.	
dolomite	4315
Total Depth.	

Tops: Topeka	3169
Lansing K.C.	3686
Viola	4111
Simpson	4176
Arbuckle	4270