


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- TRANSIT CORP.
Farm- Petrowsky No. 2

SEC. 29 T. 26 R. 12W
NE NE NW

Total Depth. 4327
Comm. 12-23-51 Comp. 1-13-52
Shot or Treated.
Contractor.
Issued. 4-5-52

County Pratt KANSAS



CASING:

8 5/8" 410' cem. w/275 sx
5 1/2" 4316 1/2' cem. w/150 sx

Elevation. 1918 KB

Production. 99 BO & 21% wtr.

Figures indicate Bottom of Formations.

soil, sand & shales	215
shale & shells	410
red bed & shells	655
shale & shell	795
anhydrite	808
red bed & shells	950
shale & shells	1360
shells & shales	1680
lime	2260
shale & lime shells	2380
lime & shale	2515
shale, lime	2645
shale & shells	2805
lime & shale	2950
shale shells	3150
lime	3235
lime sand	3345
lime	3415
chalky lime	3480
lime	3608
sand	3662
lime	4048
lime & chert lgt	4075
lime	4100
lime & chert	4137
lime	4145
lime, chert	4193
lime shale	4200
lime	4224
sand & shale	4278
lime & shale	4303
lime	4317
lime	4327
Total Depth	

Tops: K.B. meas. & substantiated by Sch.
Heebner 3489 log.
Brown Lime 3663
Lansing-K.C. 3687
Miss. 4048
Viola 4090
Simpson Shale 4194
Simpson Sand 4218
Arbuckle 4316

RTD (Schl.) 4319'