


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - MAGNOLIA PETRO. CO.
Farm - C. J. Binger No. 9

SEC. 31 T. 26 R. 12W
NE SE SE

Total Depth. 4321' K.B.
Comm. 6-2-48 Comp. 7-8-48
Shot or Treated. 500 Gals. acid
Contractor. Barnett Drilling Co.
Issued. 9-25-48

County. Pratt
KANSAS



CASING:

8 5/8" 625' Cem w/400 Sx.
5 1/2" 4297' Cem w/250 Sx.

Elevation. _____

Production. 263 Bbl.

Figures Indicate Bottom of Formations.

clay	80	Drill Stem Test 3685-3725, S.L.C. open
sand and gravel	248	30 min, rec. 30' oil cut mud,
sand	258	400# BHP.
red shale	330	Drill Stem Test 4209-29
shale	615	S.L.C. open 30 min, rec 30'
lime shells	625	drlg. mud no oil.
shale and shells	1255	Drill Stem Test 4229-54 S.L.C.
shale and lime shells	1650	open 45 min., rec. 630' oil
lime and shale	1805	cut mud & salt water, 1570# BHP.
anhydrite & shale	1865	Drill Stem Test 4296-4302, open
lime and shale	2030	30 min., rec. 70' freeoil.
lime	2105	
lime and shale	2335	Acidized w/500 Gals. acid.
lime	2415	
lime and shale	3175	
lime	3435	
lime, brkn	3485	
lime and shale	3580	
lime, brkn	3614	
lime	3650	
lime, sdy	3680	
lime	3975	
shale	3978	
lime	4010	
lime and shale	4038	
lime	4071	
shale and lime	4101	
lime and chert	4132	
shale and lime	4140	
lime	4174	
sand	4188	
shale and sand	4232	
sand	4237	
sand, hd	4249	
lime	4257	
lime and shale	4321	
total depth		K.B.

Ran Halliburton Electric Log.

Tops:

Lansing	3692'
Mississippian chat	4106
Base Mississippian	4128
Viola	4145
Simsen	4179
Arbuckle	4296

Cored 4188-93, rec. 4' shale,
slight dolomitic.
Cored 4193-4203, rec. 8' dolomite
and 1' shale 1' sand.
Cored 4203-10, rec. 2' shale, 3' 10"
sand.
Cored 4210-19, rec 8' 1" sand.
Cored 4224-29, rec 4' sand
Cored 4229-32, rec 2' 6" sand