

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - MAGNOLIA PETROLEUM CO.
Farm - C. J. Binger No. 11

SEC. 31 T. 26 R. 12W
NE NE NE

Total Depth. 4298 K.B.
Comm. 11-10-49 Comp. 11-30-49
Shot or Treated. Acid
Contractor. Barnett Drilling Co.
Issued. 1-7-50

County. Pratt
KANSAS



CASING:
8 5/8" 627' cem w/400 sx.
5 1/2" 4260' cem w/300 sx.

Elevation. _____

Production. 211 bbls. pr day.

Figures Indicate Bottom of Formations.

clay, sand	60
clay	85
sand	105
clay, sand	220
shale, shells	628
red bed	745
anhydrite	770
redbed, shells	775
shale, shells	1705
lime, shale	1745
shale shells	1780
lime	1935
lime, shale	2120
lime	2250
lime, shale	2310
shale	2405
lime, shale	3125
lime	3195
lime, shale	3260
lime	3620
lime, shale	3740
lime	4115
shale, lime	4136
lime	4168
shale, sand	4210
sand	4230
sand, shale	4260
lime, shale	4285
lime hrd	4287
lime	4289
lime wht sft	4293
lime	4298
Total depth K. B.	

Tops: K. B.	
Lansing	3696
Mississippian	4093
Base Mississippian	4109
Viola	4125
Simpson	4165
Arbuckle	4278

Ran Lane Wells Log
DST 4129-36, open 30 mins, good blow,
rec. 90' gas and oil cut mud, BHP 1050#.
Acid w/500 gals acid.