

26-26-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GULF OIL CORP.
Farm- Fred A. Hoener No. 3

SEC. 26 T. 26 R. 13W
C N/2 SE SW

Total Depth. 4365' PB 4336'
Comm. 9-29-58 Comp. 10-18-58
Shot or Treated.
Contractor. Lewis Drilg. Co.
Issued. 12-20-58

County Pratt
KANSAS



CASING:
10 3/4" 802'
7" 4356'

Elevation. 1939' DF

Production. 70 BO & 1½ BW in
24 hrs.

Figures indicate Bottom of Formations.

top soil	30
sand	280
red bed	440
shale	788
Anhydrite	815
shale & shells	1955
shale & sand streaks	2085
shale & shells	2365
lime & shale	3380
lime & shale streaks	3495
lime & shale	3630
sand	3660
shale	3730
lime & shale streaks	3790
lime & shale	3850
lime	3905
lime & shale	3969
lime	4220
chert & lime	4250
sand & shale	4284
shale	4358
shale	4365
Total Depth	
Plugged back to 4336'	

TOPS: GEOLOGIC	
Douglas	3604
Heebner	3564
Douglas Sand	3634
Brown Lime	3730
Lansing	3746
Reworked Mississippian	4147
Mississippian	4168
Reworked Viola	4196
Viola	4212
Simpson Formation	4246
Simpson Dolomite	4262
Simpson Sand	4280
Arbuckle	4356

ELECTRIC LOG TOPS	
Heebner	3564
Douglas Shale	3604
Douglas Sand	3634
Brown Lime	3730
Lansing-Kansas City	3746
Base Kansas City	4076
Rework Mississippi	4147
Mississippi	4168
Viola	4212
Simpson Shale	4246
Simpson Sand	4281
Arbuckle	4360

Acidized w/500 gal. XX-M-38 W-23 Acid.
Perf. Viola 4226-45' w/76 holes.
Acidized w/250 gal. MA and 750 gal. XX M-38 acid.