

26-26-13

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company H. L. MOORE
Farm - Hoener

No. 1


SEC. 26 T. 26 R. 13W
NE NE NW

Total Depth. 4376
Comm. 5-29-53
Shot or Treated.
Contractor.
Issued. 8-22-53

Comp. 6-19-53

County Pratt

KANSAS



Elevation. 1942 DF

Production. Pump 93 BO, no W
8 hrs.

Figures Indicate Bottom of Formations.

sand	210
red bed & lime streaks	246
red bed & shale	805
anhydrite	830
shale & shells	1525
salt	1620
shale	1750
lime	1755
shale & lime	1900
broken lime	2065
lime	2115
shale & lime	2830
shale	2975
shale & lime	3344
lime	3430
lime & shale	3633
lime	3708
lime & shale	3765
lime	4077
lime & shale	4115
lime	4157
conglomerate & lime	4195
shale	4212
lime & chert	4223
lime	4320
shale	4332
shale & lime	4360
lime	4376
Total Depth	

Snyderville shale	3577
Toronto	3584-3598
Base Oread	3598
Douglas section	3598 - 3736
Sand section	3634-3674
Brown lime	3736
Lansing	3757
Base KC	4077
Marmaton	4077-4175
Mississippi	4175 -4192
Kinderhook	4192 -4211
Viola (Chert zone 4211-51)	4211 -4256
Simpson	4256 -4355
Arbuckle	4355

TOPS: Rotary Bushing
Stone Corral Anhydrite
Tarkio Section
Topeka
Heebner
Leavenworth lime

805-828
2910
3216
3567
3573