

29-26-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- TIME PETROLEUM  
Farm- Hetrick Mowbray No. 1

SEC. 29 T. 26 R. 13W  
SE SW SE

Total Depth. 4485'  
Comm. 3-8-64 Comp. 3-19-64  
Shot or Treated.  
Contractor. Strata Drlg.  
Issued. 7-4-64

County Pratt  
KANSAS



Elevation. 1955' RB

8 5/8" 330' cem w/ 250 sx  
4 1/2" 4484' cem w/ 125 sx

Production. 65 BOPD-NW  
85

Figures Indicate Bottom of Formations.

sand	70
sand	180
shale & clay	825
shale	1550
shale & lime	3334
lime	3455
shale & lime	3830
lime	4095
lime & shale	4170
lime	4265
lime & chert	4290
chert	4305
lime & chert	4320
lime & cherty	4382
chert	4445
sand, shale-cherty	4485 RTD
Total Depth	

TOPS: SMP	
Anhydrite	813
Heebner	3631
Brown Lime	3791
Lansing	3812
Mississippi	4272
Viola	4344
Simpson shale	4446
Simpson sand	4454

DST #1 4264' 4305' tool open 2 hrs, fair blow throughout test. Rec. 900' gas, 95' oil cut mud, slight show of oil on tool. ISIP 318# in 45 min. IFP 23#, FFP 47#, FSIP 186# in 1 hr.

DST # 2 4440'-4475' Tool ope 1 hr. Rec. 100' mud, spots of oil. ISIP 1100# in 45 min. IFP 42#, FFP 73#, FSIP 1074# in 1 hr!