

Company- IRON DRILLING CO. & BROOKS HALL
 Farm- Frisbie No. 1

SEC. 21 T. 26 R. 13W
 SW SW SE

Total Depth. 4551
 Comm. 8-27-51 Comp. 9-16-51
 Shot or Treated.
 Contractor.
 Issued. 5-24-52

County Pratt
 KANSAS



CASING:
 8 5/8" 875' com. w/450 sx.
 5 1/2" 4372 com. w/100 sx. P. 3685'

Elevation. 1943

Production. Dry

Figures indicate Bottom of Formations.

sand & clay	200
sand & red bed	320
shale	430
sand, shale & shells	750
sand	765
shale & shells	1810
shale & lime	2130
lime	2265
lime & shale	3485
lime	3645
shale & lime	3920
lime	3985
lime & shale	4030
lime	4180
shale & chert	4205
lime & cherty shale	4233
shale & lime	4263
shale, chert & lime	4300
chert	4315
shale & chert	4350
shale	4380
chert	4405
chert, lime	4430
shale & chert	4450
shale & lime	4531
arb.	4551
Total Depth	

Tops: Scout	
Hoebner	3623
Brown lime	3788
Lansing	3812
Mississippi	4263
Viola	4327
Simpson	4448
Arbuckle	4531

Miss. lime 4263-4311
 Perf. 4280-4288 wtr.
 " 4262-4270 500 gal.
 acid Swb 5 gal. oil & 25 gal.
 wtr per hr.

Plugged & abd. 10-28-51
 Arb. 4531-4551 T.D. no shows
 Plugged back & set 5 1/2" 4372