

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company-SUNRAY OIL CORPORATION  
Farm- Fred Frisbie "A" No. 1

SEC. 28 T. 26 R. 13W  
NW NW SE

Total Depth. 4500  
Comm. 8-31-51 Comp. 10-3-51  
Shot or Treated.  
Contractor. Aylward Drilling Co.  
Issued. 7-11-53

County Pratt  
KANSAS



Elevation. 1947

Production. 289 bbls & no wtr

CASING:

13 3/8" 270' cem w/300 sx  
8 5/8" 916' cem w/500 sx  
5 1/2" 4500' cem w/125 sx

Figures Indicate Bottom of Formations.

surface soil, clay	28
sand, gravel	2 05
red bed	243
shale hard	262
shale	270
shale, shells	410
red bed	895
anhydrite shaley	916
red bed	1030
shale, shells	1435
salt	1620
shale	1745
shale, shells	1800
lime	1970
lime sandy	2085
lime	2240
lime sandy soft	2270
shale	2280
lime sandy	2385
lime, shale	3080
lime,	3165
lime, shale	3310
lime	3580
lime, shale	3665
shale, shells	3705
lime, shale	3795
lime	3945
lime, shale bks, & cherty	3965
lime	4062
lime, shale	4100
lime	4210
shale, lime	4250
chert lime	4270
lime	4280
lime, chert	4320
cherty lime	4343
chert	4346
shale sandy	4430
lime	4500
Total Depth	

Wops: Scout	
Heebner	3602
Brown Lime	3765
Mansing	3785
Miss.	4199
Viola	4250
Arbuckle	4436