


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SUNRAY OIL CORPORATION
Farm- Fred Frisbie No. 3

SEC. 28 T. 26 R. 13W
CS $\frac{1}{2}$ N $\frac{1}{2}$ SE

Total Depth. 4510
Comm. 5-16-52 Comp. 6-6-52
Shot or Treated.
Contractor. Stickle Drilling Co.
Issued. 9-13-52

County Pratt
KANSAS



CASING:
8 5/8" 1161' cem w/350 sx
5 1/2" 4509'

Elevation. 1948
Phys.
Production. 266 BOPD & no wtr

Figures Indicate Bottom of Formations.

sand, clay	65
sand	85
clay	100
sand	175
shale	190
red bed	715
red bed shale	860
red bed	910
anhydrite	920
shale	1045
shale, shells	1365
shale	1875
lime	2405
lime, shale	2600
lime	2680
shale	2880
lime	2992
shale	2960
shale, lime	3045
shale, shells	3225
lime, shale	3765
lime	4150
lime, chert	4170
lime cherty	4205
lime	4285
lime, shale	4304
lime	4350
lime, chert	4382
lime, shale	4445
lime	4510 RTD
Total Depth	

Tops:
Lansing 3788
Miss. 4204
Viola 4267
Simpson 4373
Arbuckle 4457

DST 4226-34 open 1 hr., Rec.
30' m, 660 FG #525,

DST 4269-85 open 1 hr. Gas 7"
rec. 3700 GO #1080;

CO 4465; 19/4332-38 swz. 15/
4315-20 PB 4305; 46/4269-84; 500-A;
Hydrafrac:/