


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- SUNRAY OIL CORPORATION
 Farm- L. E. Frisbee No. 1

SEC. 28 T. 26 R. 13W
 SE SE NW

Total Depth. 4477
 Comm. 9-14-51 Comp. 10-15-51
 Shot or Treated.
 Contractor. Stickle Drlg Co.
 Issued. 1-12-52

County Pratt
 KANSAS



Elevation. 1947

Production. Pot. 168 BOPD, nw

CASING:

13" 268'
 8" 915'
 5" 4475'

Figures Indicate Bottom of Formations.

sand	220
red bed	270
shale, shells	410
red bed	792
red bed, shells	885
red bed	890
anhydrite	912
red bed	915
red rock, shale	1225
shale, shells	1420
salt, shells	1610
shale, shells	1870
lime, shale	1945
lime	2455
lime, shale	3235
lime	3240
lime, shale	3325
lime	3610
lime, shale	3710
lime	4075
lime, shale	4113
lime	4175
lime chert	4215
lime cherty, shale	4251
shale, chert	4280
viola	4303
shale, chert	4373
lime, shale	4392
sand simpson, shale	4427
shale, sand, lime	4448
chert arbuckle	4477 RTD
Total Depth	

Tops:

Heebner	3604
Iatan	3771
Lansing	3790
Viola	4267
Simpson	4374
Arbuckle	4444

DST: 4269-80 op 1 hr rec. 50'
 mud / sso, bhp 90#.

DST: 4317-35; op 1 1/2 hr rec 30'
 socm, bhp 70#.

CO 4457; 16 holes 4438-42; 300 A;
 NS; 40/4325-35; 150 A; Test sso;
 123/4314-55; 2,000 A; 1/2 boph;
 Hydrafrac 4315-55; Test 5 3/4 boph
 / no wtr; Phy. Pot. 168 bopd no wtr.