

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock

Wichita, Kansas

Company - CONTINENTAL OIL COMPANY
 Farm - Tregellas No. 1

SEC. ~~33~~³² T. 26 R. 13W
 NE NE NE

Total Depth. 4286
 Comm. 5-11-51 Comp. 6-1-51
 Shot or Treated.
 Contractor. Anschutz Drlg Co., Inc.
 Issued. 9-22-51

County. Pratt
 KANSAS



Elevation. 1953

Production. 120 bbls

CASING:

13 3/8" 143' cem w/200 sx
 9" 859' cem w/500 sx
 5 1/2" 4260' cem w/150 sx

Figures Indicate Bottom of Formations.

surface clay	15
shale, sand, shells	167
sand-	210
shale, red bed	450
red bed, shale,	
shells	839
anhydrite	854
red rock, shale	860
shale	1140
shale, shells	1915
lime sandy	2015
shale, shells	2130
shells, shale, lime	2215
lime	2595
lime broken	2785
shale, shells	2835
lime broken	3020
lime, shale	3080
lime	3245
shale, lime	3312
shale, shells	3362
lime, shale	3422
lime	3615
shale, shells	3647
shale	3685
shale, lime	3758
lime	3786
lime brown	3811
lime K.C.	3835
lime	3989
lime, shale	4027
lime	4095
shale, lime	4130
lime	4192
shale, lime	4227
shale	4260
shale, lime	4270
chert, lime	4286
Total Depth	RTD

Tops:
 Anhydrite 839
 Lansing-K.C. 3811
 Mississippian 4263