

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

E.L.

COMPANY THE TEXAS CO.

SEC. 32 T. 26 R. 13W

FARM Chance

NO. 3

LOC. SW NE SE

TOTAL DEPTH 4435'

COMM. 3-1-51


COMP. 3-30-51

COUNTY Pratt KANSAS

SHOT OR TREATED

CONTRACTOR

ISSUED 5-19-51



CASING

10 3/4" 860' cem w/625 sxs
7" 4435' cem w/225 sxs

ELEVATION 1968 L.S.

PRODUCTION pump 130 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	220
redbed-shale-shells	415
redbed-shale	490
sand	525
redbed-shale	790
shells-redbed	828
redbed	842
anhydrite	868
redbed-shale	1175
shale-salt	1350
shale-shells	1800
shale-lime	1920
shale-lime	1987
lime	2090
lime-shale	2165
lime	2260
lime-shale	3355
lime	3425
lime-shale	3460
lime	3503
lime-shale	3543
lime	3658
lime-shale	3780
lime	4131
lime-shale	4162
lime	4229
chert-lime	4333
chert-sand	4370
lime-chert-shale	4398
lime-shale	4432
lime	4435
Total depth	

Scout tops:	
Heebner	3638
Brown Lime	3778
Lansing	3806
Viola	4298
Simpson	4350
Simpson sand	4359
Arbuckle	4432 4434
	TD 4436

*Viola/Simpson
Aug.*

*4350
9/2/51*