

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DEEP ROCK & RINE DRILLING COMPANY

SEC. 33 T. 26 R. 13W

FARM Rinaldo Calbeck NO. 6

LOC. NE NE NE

330' S. of NL, 330' W. of EL of NE/4

TOTAL DEPTH 4426

COMM. 11-14-50

COMP. 12-4-50


COUNTY Pratt

SHOT OR TREATED

CONTRACTOR R. W. Rine Drlg. Co.; Drlg. In-Handley Drlg. Co.

ISSUED 3-17-51

KANSAS



CASING

10 3/4" 798' cem. w/775sx
7" 4401' cem. w/200 sx

ELEVATION 1949 D.F.

PRODUCTION Pmp. 65 bbls. oil

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	210
shale, redbed	525
redbed	801
Anhydrite	825
shale & shells	1300
salt & shale	1890
shale & lime	2075
lime	2195
lime & sand	2375
lime & shale	2800
shale	3060
shale & sand	3200
shale	3535
shale & lime	3775
lime	4050
lime & shale	4142
lime	4200
lime, chert	4236
shale	4250
chert & lime	4290
lime, shale & sand	4366
shale	4400
lime	4405, RTD
lime	4426
Total depth	

Tops:

Heebner	3581
Brown Lansing	3745
White Lansing	3769
Conglomerate	4180
Viola	4214
Simpson	4297
Arbuckle	4400

Elev. R.B. 1952'

Record of Drill Stem Tests

#1: 3790-3811' Tool open 45 min. rec. 150' oil & gas cut mud, 90' oil. Gas to surface in 20 min. 15 minute S. I. P. 1265#.

#2: 4253-4290' Tool open 30 mins. rec. 360' oil & gas cut mud and 810' oil with mud scattered throughout. Gas to surface in 7 min. 15 minute S. I. P. 1450#.

#3: 4294-4331' Tool open 60 mins. rec. 180' oil & gas cut mud, 720' oil. Gas to surface in 10 min. 15 minute S. I. P. 1400#.