

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DEEP ROCK & RINE DRILLING COMPANY

FARM Rinaldo Calbeck

NO. 8

SEC. 33 T. 26 R. 13W

LOC. SW SE NE

330' N. of SL, 990' W. of EL of
NE/4

TOTAL DEPTH 4434

COMM. 12-21-50

COMP. 1-10-51


SHOT OR TREATED

CONTRACTOR R. W. Rine Drlg.: Drill In Folgers Drlg. Co.

ISSUED 3-17-51

COUNTY Pratt

KANSAS



CASING

8 5/8" 447' cem. w/250 sx
5 1/2" 4430' cem. w/220 sx

ELEVATION 1965' D.F.

PRODUCTION Pmp. 53 bbls. oil
per day

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	285	oil & gas cut mud, 60' muddy
redbed, shale	450	oil. Bottom hole pressure:
shale & sand	940	missed, tool did not close.
shale & shells	1800	#3 Simpson 4323-45, open 1 hr.
lime & shale	2390	Fair blow. Recovered 75' oil
shale & sand	2540	out mud. BHP 110# (15 min)
shale	2650	#4 Simpson 4345-75, open 1 hr.
lime & shale	2770	Good blow throughout. Recovered
shale	3080	270' salt water, no oil. BHP
shale & lime	3180	1420# (15 min.)
shale	3300	Swabbed well-19-51; Bailed 1 1/2
lime & shale	3400	bbls. oil per hr, no wtr.
shale & shells	3590	
shale	3660	
shale & lime	3840	
lime	3885	
lime & shale	3970	
lime	4125	
shale	4175	
lime & shale	4215	
chert, lime & shale	4260	
lime	4310	
chert & shale	4325	
lime & sand	4345	
sand	4375	
shale & lime	4434	
Total depth		

Tops:

Heebner	3606
Brown Lansing	3778
Lansing	3792
Possible Conglomerate	4174
Definite Conglomerate	4202
Kinderhook	4224
Probable Viola	4233
Definite Viola	4276
Simposn	4326
Arbuckle	4428
Elevation 1968' R.B.	
2000 gals. acid	

Record of Drill Stem Tests:

#1 Lansing Zone 3815-40, open
45 minutes. Good blow throughout.
Gas in 12 minutes. Recovered 90'
very heavily oil cut mud. 90'
muddy oil, 90' clear oil. BHP
1100# (15 minutes).
#2 Viola Chert 4275-4310, open
45 minutes. Good blow throughout.
Gas in 25 minutes. Recovered 150'