

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company - DEEP ROCK & RINE
Farm - Strait No. 3

SEC. 33 T. 26 R. 13W
NE SW NW
990' NSL, 990' EWL of NW/4

Total Depth. 4437
Comm. 6-2-49 Comp. 6-22-49
Shot or Treated. Acid, 500. @ 4437, 1000 @ 4437'.
Contractor. Rine Drlg. Co.
Issued. 9-17-49

County. Pratt

KANSAS



Elevation. _____

Production. 75 oil plus 10 water

Figures Indicate Bottom of Formations.

silt, clay	40
sand, shale	220
shale, red bed	430
redbed, shells	810
cement	810
redbed, shale	1190
shale, shells	1540
shale, salt	1700
shale, shells	1790
lime brkn	1870
lime, shale	3862
lime	4120
lime, shale	4165
Miss. lime, chert	4190
lime, chert	4235
shale, chert	4347
Core #1	4365
lime, shale	4431
lime, shale	4437
Total Depth	

Tops: (Schlumberger)

Lansing	3783
Conglomerate	4190
Viola Lime	4240
Simpson	4346
Arbuckle	4430

CORING RECORD:

#1, 4347 to 4365, rec. 15' sand and shale, 8' of sand had fair sat.

COMPLETION RECORD:

Drilled T.D. 4431.
Schlumberger T.D. 4432
Rigged up drilling in unit.
Bailed and washed hole.
Drilled cement plug to 4431, cleaned out. Drilled 4431 to 4433, lime and Dolo. white 4433 to 4435, lime & dolo., brwn. 4435-4437, lime & dolo., brwn.
Bailed hole dry, acid w/500 gals. acid. loaded hole w/96 bbls. water, Swbd
Acid w/1000 gals 15% Acid. Loaded hole with 112 bbls. water. Swbd well in. Ran tubing and rods and put on pump.

PRODUCTION RECORD:

6-22-49, 49 bbls oil, 2 1/2 bbls water, 8 hrs. Swb.
6-23-49, 69 bbls oil, 2 bbls water, 2 hrs, Swb.
7-9-49, 50 bbls. oil, 0 water, 15 hrs, pumped
7-12-49, 18 bbls, oil 0 water, 4 hrs, pumped.