

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - Rino Drilling Co.
Farm - Joe No. 1

SEC. 33 T. 26 R. 13W
NE NE SW

Total Depth. 4436

Comm. 9-18-49

Comp. 10-7-49

Shot or Treated.

Contractor. R. W. Rino Drlg. Co.

Issued. 11-5-49

County. Pratt

KANSAS



Elevation. _____

Production. Phy. Pot. 50 Bbls.

CASING:

12 $\frac{1}{2}$ " set @ 300' w/250 sx.
8 " set @ 878' w/100 sx.
5 $\frac{1}{2}$ " set @ 4432 $\frac{1}{2}$ ' w/250 sx.

Figures Indicate Bottom of Formations.

Surface dirt, sand	300
Gravel, shale	425
Red rock, shells	820
Red bed, Anhydrite	878
Red bed, shale	1345
Shale, salt	1580
Shale, shells	1820
Lime, shale	2990
Lime, sand	3030
Sandy lime, shale	3080
Lime	3205
Lime, shale	3320
Shale, lime	3660
Shale	3669
Sand	3710
Sand, shale, lime	3790
Shale, lime	3840
Lime	3945
Shale, lime	4000
Lime	4253
Lime and chert	4328
Shale, lime	4345
Sand	4360
Sand, shale	4395
Shale, lime	4435
Lime	4436

Total Depth

FORMATION TOPS:

Kansas City	3792
Conglomerate	4190
Viola	4242
Simpson shale	4330
Simpson sand	4352
Arbuckle	4432