

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company - Sunray Oil Co.
Farm - Taylor No. 2

SEC. 33 T. 26 R. 13W
SE NW NW

Total Depth. 4415
Comm. 8-31-49 Comp. 10-5-49
Shot or Treated.
Contractor.
Issued. 11-12-49

County. Pratt KANSAS



CASING:
8 5/8" set @ 795' w/550 sx
5 1/2" set @ 4415' w/150 sx.

Elevation. _____
Production. Phy. Pot. 60 Bbls.

Figures Indicate Bottom of Formations.

Soil, sand	40
Sand	125
Sand, gravel	300
Lime, shells	355
Sandy shale	475
Red bed	810
Shale, shells	1750
Lime, shale	2040
Lime, broken	2185
Lime, shale	2435
Lime	2520
Broken lime	2555
Lime, shale	2690
Shale	2870
Lime, shale	3540
Lime	3650
Broken lime	3720
Sand, shale, lime	3800
Lime	3160
Lime, shale	4190
Chert, lime	4230
Lime	4255
Chert, lime	4328
Shale	4336
Core #1 4351	
Sand, shale	4380
Shale, lime, chert	4415

Note: Surface pipe broke @ 159'
Set Halliburton plug @ 158'
Cemented w/600 sx. & 500#
calcium chloride.
Re-cemented @ 158 w/100 sx.
& 300# calcium chloride

Total Depth

FORMATION TOPS

Kansas City	3772
Conglomerate	4187
Viola	4232
Simpson sand	4334
Simpson dolomite	4355
Arbuckle	4413