

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- SUNRAY OIL COMPANY
Farm- E. V. Taylor No. 3

SEC. 33 T. 26 R. 13W
NW NW NW

Total Depth. 4448
Comm. 5-25-51 Comp. 6-16-51
Shot or Treated.
Contractor. Iron Drlg. Co.
Issued. 6-14-52

County Pratt

KANSAS



Elevation. 1955 D.F.

Production. flow 74 bbls.

CASING:

8 5/8" 864' cem. w/750 sx.
5 1/2" 4393' cem. w/400 sx.

Figures Indicate Bottom of Formations.

sand & clay	120
sand	200
red rock	290
red bed	560
sand	650
sand & red bed	850
red bed & shale	865
shale	890
red bed & shale	1250
shale, & shells	1400
shale, shells & salt	1510
shale & shells	1830
shale & lime	1897
lime	2010
lime & shale	2105
shale	2170
shale & lime	3705
shale	3800
shale & lime	3820
lime	3918
lime & shale strks	3965
lime	4177
cherty lime	4205
lime & chert	4256
cherty lime	4281
lime & chert	4315
shale	4340
shale & chert	4386
lime, shale & chert	4433
shale & chert	4448
Total Depth	

Tops:

Iatan	3775
Lansing	3798
Mississippi	4234
Viola	4346
Simpson	4437

D.S.T. 3847-71 open 1 hr., rec. 90'
) and GCM, 60' W, flow press. 55 1/2 BHP
103 O 24/4266-72 24/4262-68. Hydrafrac
4362-72, flow 74 BO per 24 hr.