


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- R. W. RINE DRILLING CO.
Farm- Briggeman "B" No. 2

SEC. 35 T. 26 R. 13W
SE NW SW

Total Depth. 4403
Comm. 5-17-55 Comp. 6-7-55
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 8-6-55

County Pratt
KANSAS



Elevation 1940 RB

Production 85 BOPD

CASING:
13 3/8 @ 251'
8 5/8 @ 1202'
5 1/2 @ 4394'

Figures indicate Bottom of Formations.

clay & sand	240	DST #5 4231-55, open 1 hr., good blow thruout, rec. 65' mud, BHP 263#/30 min.
red bed & shale	785	
anhydrite	815	
shale & shells	940	DST #6: 4255-85, open 1 hr. strong blow thruout, rec. 125' HO&GCM, 2700' gas, 60' VHO&GCM, 510' SOCSW, IFP 44#, FFP 320#, BHP 827#/30 min.
shale	1480	
shale & shells	1935	
broken lime & shale	2015	
lime & shale	2325	
shale	2665	DST #7: 4280-4320, open 1 hr. strong blow thruout, gas to surf. 20 min. rec. 130' VHO&GCM, 120' V. muddy GCO, 60' SMGCO, 658 clean gassy oil IFP 40#, FFP 150#, BHP 1050#/30 min
shale & lime streaks	2760	
shale & lime	3035	
lime & shale streaks	3115	
lime & shale	3560	
lime	3710	
lime & shale	3800	DST #8: 4390-440, open 1 hr. small blow thruout, rec. 30' SOCM, IFP 15#, FFP 28#, BHP 190#/30 min.
lime	3999	
lime & shale	4072	
lime & chert	4285	
lime	4320	Oil Shows:
lime & Arbuckle	4392	5917-19 Trace free oil, good stain, much gilsonite.
dolomite	4403	3931-37 Spotted stain, slight trace free oil.
Total Depth		3994-98 Good stain, fair show free oil ar odor
TOPS:		4042-45 Very slight trace free oil
Stone Corral (drillers)	785	4066-74 Fair show free oil, slight odor.
Leavenworth	3577	4204-13 Fair odor, slight stain, no free oil.
Snyderville	3582	4237-76 Good stain no free oil
Toronto	3593	4295-99 Slight show free oil, fair odor
Douglas	3610	4395-98 Slight show free oil, trace odor
Brown lime	3736	
Lansing	3760	
Base KC	4079	
Marmaton	4086	
Mississippi	4177	
Kinderhook	4191	
Viola	4237	
Simpson	4279	
Arbuckle	4388	

DST #1: 3908-25, open 1 hr. good blow thruout; rec. 630' gas, 65' SOCM, IFP 35#, FFP 44#, BHP 416#/20 min.

DST #2: 3987-99, open 1 hr., very small blow 25 min. flushed tool after 10 min. rec. 30' mud, BHP 95#/30 min.

DST #3: 4039-72, open 1 hr. small blow died 45 min. rec. 30' mud w/ few specks oil on tool, BHP 84#/30 min.

DST #4: 4198-4218, open 1 hr. weak blow incr. to fair by end. rec. 300' gas 30' VSOCM, IFP 15#, FFP 15#, BHP 135#/20 min.