

59790 ✓

Company - BRIDGEPORT OIL CO., INC.
 Farm - Beck "F" No. 1.

SEC. 36
 SW NW SE

T. 26 R. 13 W

Total Depth. 4395'

Comm. 12-8-43

Shot or Treated.

Contractor.


Issued. 1-29-44

Comp. 1-10-44

Rotary O-4395

County.

Pratt
 KANSAS



CASING:

8 5/8"

452' Cem.

Elevation. _____

Production.

Dry

Figures Indicate Bottom of Formations.

cellar	0-10	chert ✓	4104
clay	60	lime & shale	4132
sand	170	shale	4157
clay yellow & sand	230	chert	4180
clay red	260	shale	4184
red rock	350	shale & chert	4190
red bed	452	shale	4197
red rock & shale	764	chert & shale	4225
anhydrite	786	chert	4232
red rock & shale	1035	shale	4237
shale & shells	1280	sand	4242
salt & lime shells	1297	sand & shale	4262
shale & shells	1635	sdv lime	4283
shale & sdv shells	1725	shale	4285
lime & shale	1807	shale, sand, chert	4307
lime	2025	shale	4334
lime, shale & red rock	2040	sand & shale	4350
shale, sand & red rock	2074	shale	4355
shale, red rock & shells	2094	lime	4395
sand	2102	Total Depth.	
shale, red rock & shells	2158		
lime & shale	2352	Formation Tops-D.F.	
lime	2425	Miss. Lime	4155
lime & shale	2483	Kinderhook	4178
lime brkn	2562	Viola	4195
lime & shale brks	2612	Simpson	4229
lime & shale	2785	Arbuckle	4351
shale & shells	2827		
shale	2853		
shale & lime	2871		
shale & lime shells	2905		
lime & shale	2932		
shale	2940		
lime	2972		
lime & shale	3050		
lime sdv	3080		
lime & shale	3270		
lime	3363		
lime sdv	3387		
lime	3487		
shale	3530		
lime	3612		
sdv shale	3640		
shale & lime	3655		
lime	3705		
shale	3751		
lime & shale	3798		
lime	3811		
lime, shale, red rock	3825		
lime & shale	3834		
chert & lime	3850		
lime & shale	3856		
chert & lime	3862		
lime, shale, chert ✓	3871		
lime & shale	3915		
lime	3966		
lime & shale	3997		
3997 equals 4010			
lime & shale	4010-4027		
lime, shale, chert ✓	4032		
lime & shale	4100		